

11-28-2E


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS COMPANY
Farm - M. C. Devine No. 1

SEC. 11 T. 28 R. 2E
NEc SE

Total Depth. 3350' ✓
Comm. 3-19-47 Comp. 4-8-47 ✓
Shot or Treated.
Contractor. Wakefield Drlg. Co.
Issued. 5-10-47

County. Sedgwick
KANSAS



CASING:
8-5/8" OD 118' Cem. w/50 sx

Elevation. 1349 act v rh

Production. Dry

		Figures Indicate Bottom of Formations.	
surface soil	115	lime brkn & shale	2936
shells & slate blue	136	Miss. lime	2960
shale & shells	165	lime	3008
sand	175	lime & shale brks	3040
shale & shells	370	lime	3058
lime	395	lime & shale strks	3080
shale, shells & lime	530	lime & shale	3230
lime & shale	565	sand & shale	3237
shale & shells	620	lime sdy	3240
lime	648	shale & lime	3280
sand	665	lime & sand	3288
shale & shells	705	shale sdy	3303
lime	719	sand hrd wh	3307
shale	735	sand & lime	3310
shale & lime	745	lime	3330
lime	768	lime hrd	3347
shale	773	lime sft	3356
lime	810	corr Sch Depth	3350
lime & shale	855	Total Depth	
shale, lime strks	960		
shale & lime shells	1054		
shale sdy	1065	Tops:	
sand & shale	1112	Lansing	2130
lime sdy	1128	Kansas City	2454
shale sdy	1164	Mississippi	2931
lime brkn	1245	Simpson	3232
shale & lime shells	1362	Arbuckle	3301
lime	1372		
lime & shale	1490	Ran DST, set packer at 3226'	
lime brkn	1538	w/14' anchor, open 30 minutes,	
shale & lime	1572	filled up 2400' w/salt wtr-	
lime	1588	Ran Schlumberger, 4-8-47, no	
lime & shale	1604	show.	
lime	1644		
shale	1664		
sand & iron strks	1682		
lime	1738		
shale & shells	1758		
lime	1806		
shale & lime	1838		
lime brkn	1874		
lime & shale	1904		
lime	1926		
lime & shale	1958		
sand	1988		
sand & shale sdy	2015		
shale	2082		
lime & shale strks	2118		
lime	2154		
shale	2184		
lime	2276		
shale & shells	2370		
shale	2462		
lime	2685		
shale & lime strks	2734		
lime	2780		
lime brkn	2860		