

T.C. JOHNSON.
Lula Jansen No. 1.

SEC. 11 T. 28 R. 2E.
SWc NW

Total Depth. 3404
Comm. 1-27-36 Comp. 3-31-36
Shot or Treated.
Contractor. Advance Drlg Co.
Issued. 4-11-36.

County. Sedgwick.

CASING.

15 $\frac{1}{2}$ " 120' 8" 2705' UR 2975'
12 $\frac{1}{2}$ " 738'
10" 2148'

Elevation.

Production. DRY

Figures Indicate Bottom of Formations.

cellar	10	lime	865	Kansas City lime	2590
clay yellow	40	shale	880	sdv lime	2610
clay	60	lime	890	HFV 2590-2610	
clay yellow	80	shale	900	lime	2695
shale blue	95	lime	920	shale	2697
gravel 2 EWPFR	97	slate	955	lime	2717
slate blue	100	lime	960	shale	2725
gravel 10 EWPFR	115	slate	1010	shale blk	2740
slate blue	120	lime	1025	shale grey	2750
lime	132	shale	1125	lime	2755
slate blue	140	water sand 1 $\frac{1}{2}$ EWPFR	1130	shale	2785
lime	160	lime hard	1137	lime	2800
shale light	170	slate	1200	shale	2810
lime hard	178	lime	1210	lime	2815
lime broken	190	shale	1225	shale	2830
shale	195	lime	1250	lime	2850
lime	215	slate	1255	shale	2855
shale blue	220	lime	1310	lime	2860
lime	270	shale	1330	shale	2865
shale and shells	285	lime	1340	shale and shells	2875
slate blue	290	shale	1410	lime	2880
lime	295	lime	1460	shale	2940
red rock	325	slate	1475	lime	2950
lime hard	360	lime	1492	shale	2955
lime broken	370	shale	1545	red rock	2975
lime	395	lime 1EW 1550-55	1590	chat	2980
shale blue	398	slate	1630	light show oil and gas	
shale and shells	405	lime	1660	at 2975-80	
lime	475	shale	1665	chat	3050
shale	485	lime	1670	trace oil 3021-28	
red rock	490	shale	1685	$\frac{1}{2}$ EWPFR 3028-35	
lime	500	lime	1695	small show oil 3035-40	
shale	510	shale	1745	lime and chat	3080
lime	530	lime	1752	lime	3165
slate blue	535	shale and shells	1760	shale	3170
lime	580	lime hard	1770	lime	3186
red rock	585	shale	1775	shale green	3206
lime	600	lime	1800	lime	3232
shale	605	shale	1805	shale blk	3290
lime	630	lime	1820	reduced hole to 6" at	
shale	650	shale	1840	3270	
lime	690	lime	1880	Misner sand(wtr)	3294
slate and shells	700	shale	1895	Viola cherty lime	3305
lime	710	lime	1932	Wilcox sand	3355
sand	735	shale	1940	sand & green shale	3370
2 EWPFR 710-15		shale and shells	1950	Siliceous lime	3405
HFV 715-25		lime	1971	Total Depth.	
slate blue	740	shale	1980	3405 equals 3404 cable	
lime	748	lime	1984	correction.	
red rock	750	shale	1990		
shale	755	lime	2000	No shows of oil below	
lime	765	shale	2140	chat. Had 2800 ft of	
slate white	775	lime	2150	water in hole at 3404.	
lime	780	shale	2180	Dry and abd.	
shale and shells	800	lime	2225		
shale	825	sdv lime soft	2245		
lime	845	shale	2320		
shale	855	lime	2330		
lime broken	860	shale	2520		