

OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

February 12, 1980

Jay Evans Oil Company
221 South Colborn
Iola, Kansas 66749

Gentlemen:


Attached hereto are the results of tests run on the rotary core taken from the Simmons Lease, Well No. 10, located in Section 23, T-28S, R-20E, Neosho County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and submitted to our laboratory on February 2, 1980.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES


Sanford A. Michel

SAM/kas
5 c to Iola, Kansas

OILFIELD RESEARCH LABORATORIES

LOGName Jay Evans Oil Company Lease Simmons Well No. 10Depth Interval,
FeetDescriptionBARTLESVILLE SAND

495.0 - 496.3	Brown sandstone.
496.3 - 496.6	Gray sandy shale.
496.6 - 497.6	Brown sandstone.
497.6 - 497.8	Gray shale.
497.8 - 499.9	Brown sandstone.
499.9 - 500.9	Brown shaly sandstone.
500.9 - 502.1	Brown sandstone.
502.1 - 502.6	Brown shaly sandstone.
502.6 - 503.0	Gray shale.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Jay Evans Oil Co. Lease Simmons Well No. 10

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	495.5	19.4	34	40	74	512	73.
2	496.7	19.1	42	29	71	622	61.
3	497.5	18.0	54	26	80	754	18.
4	498.5	15.8	45	36	81	552	16.
5	499.5	19.4	47	27	74	707	81.
6	500.7	21.1	52	41	93	851	5.3
7	501.5	18.8	37	46	83	540	25.
8	502.5	13.6	45	31	76	475	2.6