

MITCHELL Well no. New 2 SW¹/₄ OF SEC. 20-28-20, Neosho County, Kansas

<u>Thick- ness</u>	<u>STRATA</u>	<u>DEPTH</u>	<u>REMARKS</u>
35	Soil, clay, sand	35	
20	Lime	55	
14	Shale	69	
5	Lime	74	
32	Shale	106	
21	Lime	127	
5	Shale	132	
21	Lime	153	
32	Shale	185	
15	Sand	200	
23	Shale	223	
43	Lime	266	
48	Shale	314	
20	Lime	334	
8	Shale	342	
7	Lime	349	Casing 364'
108	Shale	457	
2	Lime	459	
69	Shale	528	
5	Oil sand fair show	533	
5 ¹ / ₂	Oil sand fair show	538 ¹ / ₂	
5	Oil sand fair show	543 ¹ / ₂	
2	Oil sand fair show	545 ¹ / ₂	

20 sacks cement on packer set at 533'
 Drive pipe 36-4 overall
 Cemented back to 541'
 Packer seat & nipple & collar 533'
 Bottom of hole 541'
 Pulled pipe

Completed March 4, 1953

3/9/53 Sandoil job: 90 bbls. crude - 70 heavy
 4000# fine sand
 Morflo - 15 gal.

2/16/54 Sandoil job: 125 bbls. light crude
 4000# fine sand

KEAS DONATION
 SEPTEMBER 1991