

KEAS DRILLING COMPANY
Chanute, Kansas

Heady N-5 E $\frac{1}{2}$ NE $\frac{1}{4}$ SEC. 30-28-20, Neosho County, Kansas

<u>No. Feet Strata</u>	<u>Formation</u>	<u>Depth of hole</u>	<u>Remarks</u>
2	Top soil	2	
24	Clay	26	
8	Sand	34	Drive pipe at 34'
7	Lime	41	Water at 41'
12	Shale dark water	53	
5	Lime	58	
9	Shale	67	
4	Lime	71	
31	Shale	107	
24	Lime shells	131	
8	Shale	139	
11	Lime	150	
2	Shale	152	
3	Lime	155	
46	Shale light	201	
7	Lime	208	
20	Shale	228	
40	Lime	268	
7	Shale dark	275	
36	Shale	311	
22	Lime	333	
13	Shale	346	
5	Lime	351	
7	Shale dark	358	
76	Shale	434	Set 6 $\frac{1}{4}$ at 366'
1	Lime	435	
5	Shale dark	440	
16	Shale light	456	
2	Lime	458	
72	Shale	530	
17	Sand oil	547	
2	Coal	549	
13	Shale white	562	Plugged back to 547' Packer set at 528' Outside 459' Inside 548' Fluid 60'

Well completed 4/23/54
Sandoil job: 105 bbls. crude same field
4000 lbs. sand fine

KEAS DONATION
SEPTEMBER 1994

KEAS DRILLING COMPANY, INC.,
Chanute, Kansas
January 1, 1956

ERIE PROPERTIES

Heady, A. Lease: 80 Acres

INVENTORY

No. Wells 11

8	Pumping
3	Injection
8	2D Jensen Pumping units (New 1953)
1500'	6 1/2 casing (used)
1500'	2" C. W.
1500'	5/8 Rods
2500'	1" C. W. 1.75 lbs
2500'	2" seamless 4.60 lbs
2000'	2" C. W. oil lines (new)
1400'	2" C. W. water lines
8	New Huff insert barrels - 8 cup
8	1HP 3 phase 220-440 electric Motors (New)
8	Disconnect switches
8	Starter switches
3	Water meters complete
1500'	2" C. W. tubing (water wells)
22	25' electric poles (new)
8	12' electric poles (new)
4000'	No. 4 bare electric wire (new)
6000'	No. 6 bare electric wire (new)
1	140 barrel steel welded tank
1	40 barrel wood gun barrel
600'	5" water line from Erie

KEAS DONATION
SEPTEMBER 1951

KEAS DONATION
SEPTEMBER 1951

KEAS DONATION

SEPTEMBER 1951