

29-28-20E

SUTCLIFFE PIPE & SUPPLY

JOE SUTCLIFFE

PHONE 1644 CHANUTE
PHONE 7-1062 WICHITA

Well Record

119 S. GRANT, CHANUTE, KANSAS
5705 N. BROADWAY, WICHITA, KANSAS

COMPLETE LINE OF NEW & USED PIPE - BELTING - STORAGE TANKS - WIRE LINES

Well No.	6	Farm	Noaks	Producer	Keas Drilling Company		
Location		Sec.		Twp.	Rg.		
Elevation		State	Kansas	County	Neosho		
Kind (Oil, Gas, Water, Dry Hole)	Oil	Contractor	Joe Sutcliffe				
Producing formation		Top		Bottom			
Shot with		qts.		from		to	
Packer set at	526'	Kind		Size			
Liner	from	to		Perforated from		to	

LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
2	Soil	2	12	Sand	536
38	Clay	40			
10	Lime	50			
4	Slate	54			
6	Lime	60			
3	Slate	63			
12	Lime	75			
31	Shale	106			
46	Lime	152			
2	Shale	154			
2	Lime	156			
18	Shale	174			
6	Sand	180			
4	Shale	184			
16	Sand	200			
21	Shale	221			
44	Lime	265			
25	Shale	290			
6	Sand	296			
13	Shale	309			
21	Lime	330			
8	Slate	338			
7	Lime	345			
1	Shale	346			
3	Slate	349			
110	Shale	459			
3	Lime	462			
4	Slate	466			
14	Shale	480			
10	Sand	490			
34	Shale	524			

To Total Depth 536'

Open Hole

Casing 8" at 86'

Casing 6 1/2" at 352'

Casing 2" at 526'

Cement 18 sacks

Tubing all casing pulled

Rods

Additional Information

water at 54'

water at 63'

water at 338'

run SLM at 508'

good show of oil at top of sand

run SLM on cement at 456' - run slm inside of tubing - 536'; load hole with water before pulling casing.

16 SAX Cement

1 1/2" Seamless

KEAS DONATIONS
SEPTEMBER 1955

Date Completed 9-15-55
date started 9-2-55

O. K.

Superintendent