

29-28-20E

SUTCLIFFE PIPE & SUPPLY

JOE SUTCLIFFE

Well Record

PHONE 1644 CHANUTE
PHONE 7-1062 WICHITA

119 S. GRANT, CHANUTE, KANSAS
5705 N. BROADWAY, WICHITA, KANSAS

COMPLETE LINE OF NEW & USED PIPE - BELTING - STORAGE TANKS - WIRE LINES

Well No. 6 Farm Pence-Central Producer Keas Drilling Company

Location _____ Sec. _____ Twp. _____ Rg. _____

Elevation _____ State Kansas County Neosho

Kind (Oil, Gas, Water, Dry Hole) Oil Contractor Joe Sutcliffe

Producing formation _____ Top _____ Bottom _____

Shot with _____ qts. _____ from _____ to _____

Packer set at 521' Kind _____ Size _____

Liner _____ from _____ to _____ Perforated from _____ to _____

LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
2	Soil	2	14	Sand	534
33	Clay	35		BOTTOM OF HOLE	
2	Gravel	37			
8	Lime	45			
3	Slate	48			
12	Lime	60			
4	Slate	64			
11	lime	75			
10	sand	85			
18	shale	103			
50	lime	153			
5	shale	158			
5	sand	163			
15	shale	178			
32	sand	210			
13	shale	223			
40	lime	263			
6	slate	269			
16	shale	285			
12	sand	297			
11	shale	308			
20	lime	328			
3	slate	331			
6	shale	337			
8	lime	345			
2	slate	347			
3	shale	350			
4	lime	354			
94	shale	448			
2	lime	450			
170	shale	520			

To Total Depth

Open Hole

Casing 8" at 85'

Casing 6 1/2" at 355'

Casing 2" at 521'

Cement 2 gallon Konset

Tubing

Rods

Additional Information

water at 37'

water at 48'

water at 64'

SLM at 509' 6"

plugged back to 528',

run SLM on outside of tubing, top of cement 379'; run SLM on inside of tubing 527' 6"; load hole w/water, pulled all 6 1/2" & 8" casing - 95' of oil in hole.

J-55 Seamsless

KEAS DONATION

KEAS DONATION
SEPTEMBER 1991

SEPTEMBER 1991

Date Completed Sept. 27, 1955

O. K.

date started Sept. 16, 1955

Superintendent