

21-28-20E

SUTCLIFFE PIPE & SUPPLY

JOE SUTCLIFFE

PHONE 1644 CHANUTE
PHONE 7-1062 WICHITA

Well Record

119 S. GRANT, CHANUTE, KANSAS
5705 N. BROADWAY, WICHITA, KANSAS

COMPLETE LINE OF NEW & USED PIPE - BELTING - STORAGE TANKS - WIRE LINES

Well No. 7 Farm Pence-Central Producer Keas Drilling Company

Location _____ Sec. _____ Twp. _____ Rg. _____

Elevation _____ State Kansas County Neosho

Kind (Oil, Gas, Water, Dry Hole) Oil Contractor Joe Sutcliffe

Producing formation _____ Top _____ Bottom _____

Shot with _____ qts. _____ from _____ to _____

Packer set at 522' Kind _____ Size _____

Liner _____ from _____ to _____ Perforated from _____ to _____

LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
2	Soil	2			
34	clay	36			
2	Gravel	38			
8	lime	46			
2	slate	48			
12	lime	60			
4	slate	64			
12	lime	76			
32	shale	108			
52	lime	160			
20	shale	180			
26	sand	206			
20	shale	226			
42	lime	268			
4	slate	272			
18	shale	290			
10	sand	300			
14	shale	314			
22	lime	336			
3	shale	339			
6	slate	345			
5	lime	350			
3	slate	353			
5	lime	358			
102	shale	456			
3	lime	459			
46	shale	505			
4	slate	509			
12	shale	521			
14	sand	535			
BOTTOM OF HOLE					

To Total Depth 535'

Open Hole _____

Casing 8" at 89'

Casing 6 1/2" at 360'

Casing _____ at _____

Cement 18 1/2 sacks & 2 gal. Konset

Tubing 2" 522'

Rods _____

Additional Information _____

water at 46'

water at 64'

SLM - 508' 6"

run SLM outside of tubing on top of cement - 389'; run SLM on inside of tubing - 527' 6"; pulled all 6 1/2" & 8" pipe

Plugged back to 528' - 1 1/2 sacks cement

J-55 Seamless

Pack Sand, but had very good show

KEAS DONATION

Date Completed Oct. 10, 1955
date started sept. 29, 1955

O. K.

SEPT 1955
Superintendent