

SUTCLIFFE PIPE & SUPPLY

JOE SUTCLIFFE

PHONE 1644 CHANUTE
PHONE 7-1062 WICHITA

Well Record

119 S. GRANT, CHANUTE, KANSAS
5705 N. BROADWAY, WICHITA, KANSAS

COMPLETE LINE OF NEW & USED PIPE - BELTING - STORAGE TANKS - WIRE LINES

N6

Well No. 5x	Farm Pence-Central	Producer Keas Drilling Company
Location	Sec.	Twp. Rg.
Elevation	State Kansas	County Needhso
Kind (Oil, Gas, Water, Dry Hole) Oil	Contractor Joe Sutcliffe	
Producing formation	Top	Bottom
Shot with	qts.	from to
Packer set at 529'	Kind	Size
Liner	from to	Perforated from to

LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
2	Top Soil	2	14	Sand	490
41	Clay	43	34	Shale	524
5	Lime	48	4	Sand Oil	528
3	Slate	51	9	Sand Oil	537
15	Lime	66			
3	Slate	69			
7	Lime	76			
5	Sand	81			
28	Shale	109			
5	Lime	114			
6	Shale	120			
40	Lime	160			
15	Shale	175			
5	Lime	180			
5	Shale	185			
25	Sand	210			
38	shale	228			
42	Lime	270			
5	slate	275			
39	shale	314			
22	lime	336			
3	shale	339			
4	slate	343			
8	lime	348			
2	slate	350			
3	shale	353			
3	lime	356			
105	shale	461			
3	lime	464			
7	slate	471			
5	shale	476			

To Total Depth **537'**

Open Hole

Casing **8 1/2"** at **85'**
Casing **6 1/2"** at **358'**
Casing **8"** at **529'**

Cement

Tubing

Rods

Additional Information

water at 51' } 22 Bucyrus Erie
water at 69' } Not right
water at 343'
gas at 490' and 528'
Oil at 537'

529' of 2" tubing, set packer at 529'
21 sacks cement, pull all 6 1/2"

J55 Tubing
Seating nipple

21 sacks cement

very good show from 529 to 537

KEAS DONATION

SEPTEMBER 1991

Date Completed **8-19-55**
date started **8-9-55**

O. K.

Superintendent