

WELL RECORD

Well No. 1. Farm Erney Producer Wayne E. Wild
 Location _____ Sec. _____ Twp. _____ Rg. _____
 Elevation _____ State Kansas County Neosho
 Kind (Oil, Gas, Water, Dry Hole) Dry Hole Contractor Evans & Son.
 Producing formation None Top _____ Bottom _____
 Shot with _____ qts. _____ from _____ to _____
 Packer Set at _____ Kind _____ Size _____
 Liner _____ from _____ to _____ Perforated from _____ to _____

LOG

Thick-ness	Strata	Depth	Thick-ness	Strata	Depth
4	topsoil	4			
11	sandrock	15			
10	lime	25			
35	lime broken	55			
21	lime	71			
46	shale	117			
28	lime	145			
8	slate blk.	153	-	water	
72	shale	225			
10	sand & lime	235			
2	shale	237			
8	lime	245			
65	shale	310			
46	lime 40'	356			
46	shale d. gas.	402			
21	lime 20'	423			
7	shale d.	430	-	water	
5	lime 5'	435			
4	shale d.	439			
78	shale sandy	517			
2	lime 2'	519			
23	shale	542			
2	lime	544			
6	shale blk.	550			
44	shale	594			
41	shale sandy	635			
15	light shale	649			
11	white shale	660			
6	red bed	666 td.			

Total Depth 666'

Open Hole _____

Casing 8" drivepipe at 11' cemented

Casing 7" at 47216 pulled.

Casing _____ at _____

Cement _____

Tubing _____

Rods _____

Additional Information This well was

saved for a water well. Put 100'

mud on bottom, run 3 sacks of

cement on mud. Set rock bridge

at 200', run 6 sacks of cement on

bridge. Drivepipe was cemented

with 2 sacks.

*611-613 light
Oil odor, dark sand
did not wash.*

KEAS DONATION

SEPTEMBER 1991

Date Completed November 19, 1955

O. K. Jim Evans Jr.

Superintendent