



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS - PHONE HE1-2650

March 11, 1966

Stan Cannan
701 South Highland
Chanute, Kansas

Dear Sir:

Attached hereto are the results of tests run on the Bartlesville formation Rotary core taken from the Blaine Lease, Well No. 3, located in Section 23, T-28S, R-20E, Neosho County, Kansas, and submitted to our laboratory on March 8, 1966.

This core was sampled after being recieved in the laboratory.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Benjamin R. Pearman
Benjamin R. Pearman

BRP:rf

5 c.

OILFIELD RESEARCH LABORATORIES

-LOG-

Company Stan Cannan Lease Blaine Well No. 3

Depth Interval, Description
Feet

484.0 - 489.0 - Brown shaly sandstone.

489.0 - 490.0 - Shale.

490.0 - 491.0 - Dark carbonaceous sandstone.

491.0 - 493.0 - Shale.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1-B

Company Stan Cannan Lease Blaine Well No. 3

Sample No.	Depth, Feet	Effective Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.	Feet of Sand		Total Oil Content	Perm. Capacity Ft. X md.
			Oil	Water	Total			Ft.	Cum. Ft.		
1	484.5	20.4	43	25	68	682	26.				
2	485.5	13.7	35	53	88	372	Imp.				
3	486.5	17.4	42	31	73	569	8.7				
4	487.5	19.4	45	26	71	679	71.				
5	488.5	19.4	45	22	67	679	16.				
6	490.5	17.3	47	30	77	632	0.47				