

hbs

Company:

Sec. 6 T. 28 R. 22

Farm: McClintick # 16

Loc:

Total depth: 402'

County: Crawford

Comm:

Elevation:

Comp: Dec. 1940

Left 10 Ft. of
6-1/4 casing in well.

Yellow sandy clay	8'	
Light gray shale	15	
Light gray sandy shale	30	
Light sandy hard	35	
Light gray sandy shale	70	
Dark gray shale	84	
Lime	86	Pawnee
Dark gray shale break	90	
Brownish lime	100	
Lime, 1' break at	112	
Dark shale	132	
Dark shale	137	
Hard sandy light gray shale	147	
Gray shale	152	
Hard sandy light shale	157	
Gray shale	162	
Gray shale	172	
Dark gray shale	190	
Lime	213	Ft. Scott
Shale b r e a k	220	
Lime	225	
Dark shale	240	
Gray shale	245	
Dark gray shale	255	
Light gray shale	260	Well
Reduced	285	
Gray shale	300	
Light shale	317	
Dark shale	320	
Lime 2'	325	
Gray shale	330	
Light sandy shale	345	
Light gray shale	355	
Gray shale	370	
Dark green shale	389	
Light shale		
Brown sand Firm		
GOOD	391	Show OIL
Same	393	" "
Dark sand GOOD SHOW	396	of OIL
Sandy shale	402	