

Company:

Location: Sec. 6 T. 28 R. 22

Farm: McClintick #9

County: Crawford

Total Depth: 435'

Comp:

Comm:

Elevation

Bottom of tubing at 412', 275 feet of 4-7/8 Casing, 7 feet 6-1/4 casing

7 Yellow clay
10 Sand and yellow clay
35 Gray sandy shale
50 Light and sandy shale
60 Light sandy shale
65 Sandy lime, some water
70 Gray shale PAWNEE LIME top 85' B-130'
85 Dark shale
105 Lime
107 Shale, break, some water
130 Lime
140 Gray shale
155 Dark shale
180 Light gray shale, sandy
190 Dark gray shale
199 Dark shale Top 199' Bottom 217
217 Lime FORT SCOTT, GAS
224 Dark shale, break
230 Lime, Bottom of OSWEGO
235 Dark slate, GAS and WATER
250 Dark gray shale
260 Dark shale
270 Gray and brown shale
275 Gray shale cased at 275'
295 Gray shale
300 Sandy lime and sand
315 Light shale gray
320 Dark shale break
325 Dark gray shale
333 Dark shale
336 Dark shale
339 Broken lime and shale, GAS 338
350 Light gray shale
355 Dark shale
375 Gray shale
390 Light sand, some shale
393 Gray sandy shale
395 Light sand SHOW of OIL
397 Fair show OIL Gray sand
400 Gray sand FAIR OIL
404 Gray sand FAIR OIL
410 Dark shale, sandy
424 Dark shale
429 Coal and shale
435 Gray shale
END