

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGState Geological Survey
WICHITA, BRANCHAPI No. 15 — 037 — 20,412
County NumberS. 27 T. 28 R. 22 E
Loc. 1250' FSL; 900' FWL of SW,
County Crawford

Operator

L & L Oil Company

Address

P.O. Box 13, Benedict, Kansas 66714

Well No.

10

Lease Name

Wintjen

Footage Location

1250'

feet from (N) (S) line

900'

feet from (E) (W) line

Principal Contractor

Company Tools

Geologist

Spud Date

Oct. 4, 1979

Date Completed

Oct. 10, 1979

Total Depth


421'

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

Square Deal Oil Co., Inc.

640 Acres
N

Locate well correctly

Elev.: Gr.

DF

KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9 5/8"	7"	17#	52'	Portland A	16	
Production	4 3/4"	2 7/8"	6 1/2#	420'	Portland A	51	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	2 1/8" Alum	366' - 384'
TUBING RECORD					
Size	Setting depth	Packer set at			
1"	400'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Fracture with 100 sacks of sand and 250 bbl water	366' - 384'

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
Dec. 20, 1979	Pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	5 bbls.		5 MCF		
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator L & L Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 10	Lease Name Wintjen	Oil
S 27 T 28 R 22 E		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil		10		
Shale		40		
Lime		90		
Coal		94		
Shale		153		
Lime		180		
Coal		184		
Lime		192		
Coal		195		
Shale		360		
Oil Sand		390		
Shale		421		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature <i>Lawrence J. Smith</i>
	Owner
	Title
	Date

966085