


WELL COMPLETION REPORT AND
DRILLER'S LOG

S. 33 T. 28 R. 22 E

Loc. 480' NSL & 150' WEL E2 NE

County Crawford

640 Acres
N

Locate well correctly

Elev.: Gr. _____

DF _____ KB _____

API No. 15 — 037 — 20,431 ✓
County Number

Operator

Stephens Oil Co.

Address

Box 144 Walnut, Kansas

Well No.

7

Lease Name

Myers

Footage Location

480' feet from (N) (S) line 150' feet from (E) (W) line

Principal Contractor

Fidelity Drilling Co.

Geologist

Spud Date

11-15-79

Date Completed

12-21-79

Total Depth

373

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

Producers Group

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8"	6 1/4		52'	Surface	7	Regular
	6 1/4	2 3/8	3.70	373'	Regular	95	Prum Gel 2%

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at
1"	371	373

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
25 sacks 20-40 sand	373' - 387'
4 " 10-20 "	
50 lbs. Water Gel	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
12-22-79		Pumping			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
1		bbls.	—	MCF	bbls. — CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. H 7	Lease Name Myers	Oil
S 33 T 28 R 22 E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil	0	2		2
Sand Rock	2	4		4
Shale	4	77		77
Lime	77	114	40 FT.	114
Shale	114	124		124
Lime	124	126		126
Shale	126	160		160
Shale	160	183		183
Lime	183	205	20 FT.	205
Shale	205	211		211
Lime	211	217	5 FT.	217
Shale	217	315		315
Lime	315	317	2 FT.	317
Shale	317	373		373
Sand	373	387	Bartlett	387
Shale	387	392		392 T.D.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature Morris S. Stephens
	Title Owner
	Date 1-21-80