

SUTCLIFFE PIPE & SUPPLY ORIGINAL

JOE SUTCLIFFE

PHONE 1644 CHANUTE
PHONE Temple 8-3801 WICHITA

Well Record

118 S. GRANT, CHANUTE, KANSAS
6705 N. BROADWAY, WICHITA, KANSAS

COMPLETE LINE OF NEW & USED PIPE · BELTING · STORAGE TANKS · WIRE LINES

Well No.	6	Farm	Harris	Producer	Sutcliffe Pipe & Supply	
Location	NE NW NE			Sec.	34	Twp. 28 Rg. 22
Elevation				State	Kansas	
Kind (Oil, Gas, Water, Dry Hole)				Contractor	Sutcliffe Pipe & Supply	
Producing formation				Top	Bottom	
Shot with				qts.	from	to
Packer set at				Kind	Size	
Liner				from	to	Perforated from to

LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
8	Soil & clay	8			
2	Sandrock	10			
57	Shale	67			
17	Lime	84			
2	Shale	86			
18	Lime	104			
49	Shale	153			
12	Sand - show of oil	165			
8	Shale	176			
18	Lime (OSW)	191			
9	Shale	200			
5	Lime	205			
100	Shale	305			
2	Lime	307			
71	Shale	378			
1	Coal	379			
3	Sandy shale	382			
11	Sand (oil)	393			
2	Shale	395			

Total Depth 395'

Open Hole

Casing at

Casing at

Casing at

Cement

Tubing

Rods

Additional Information

165' - show of oil

Run drill pipe in hole - put valves in pump & prime - rim hole from 379 to 395

Circulate hole clean - pull drill pipe -

Run 2" with packer & perforation -

Top of packer set at 382' - seating nipple at 383 1/2' - 12' of perforation - run 1" outside of 2" put 5 sacks cement on top of packer - pull 1" pipe - Run 1" to bottom - circulate hole clean - put 2' of cement on bottom - plugged back to 393' - pull 1" - tear down & move.

Completed Nov. 18, 1959

O. K.

Started Nov. 11, 1959

Superintendent

376