

Sec. 2, T 28 S., R. 23 E.

Year Well Reported _____

API Serial Number 15 237-20056

KANSAS WELL COMPLETION REPORT

2-28-23E

INSTRUCTIONS: Within 30 days after completion of this well the owner or operator should complete the form and mail it to Margaret Oros, Chairman, AAPG-CSD District 12, State Geological Survey of Kansas, Lindley Hall, Lawrence, Kansas 66044, in the enclosed stamped, self-addressed envelope. (The information given in the IEM print-out is taken from the "Intents-to-Drill" list of the Oil and Gas Conservation Division of the State Corporation Commission of Kansas, 500 Insurance Building, Wichita, Kansas 77602. Please correct any item that is in error.)

Craufnd Co.

SE NE

Well-Kans. Oil Co. # 23 Holtman

Date Drilling Began: June 16-1965

Date Drilling Completed: June 25-1965

Hole completed as (check): Dry ☐;

Oil ☒; Gas ☐; Service well ☐

Total depth of hole: 165 1/2 feet

Name of formation at total depth: _____

If OWWO*, give new footage drilled: _____

Field Name: Holtman

Name of Company purchasing oil or gas: Mid-America Ref Co - Chanute, Mo


Initial Potential or Production: Barrels of oil/day 2;

Barrels of water/day 15;

Oil Gravity 33 °API;

Net Pay Thickness 12 Ft.;

Please show location of well in section:



Elevation: Derrick floor _____

Kelly Bushing _____ Ground _____

Electric or other logs were run: Yes ☐ No ☒

Well was Cored: Yes ☒ No ☐

Drill Stem Test Run: Yes ☐ No ☐

Thousand cu ft gas/day 0

Pay Depth (Bottom) 156

Name of Pay Zone Peru Sand

Please use other side of sheet for additional information. Copy of driller's log, electric logs, and other well information would be appreciated. (* OWWO - Old hole re-worked or deepened.)

The AAPG's Committee on Statistics of Drilling (CSD) on January 1, 1966 began compiling data on wells reported drilled in the U. S., Canada, and Mexico. The Oil and Gas Journal has contracted to publish weekly statistical summaries of the data. These will be used by the International Oil Scouts Assoc. American Petroleum Inst., U. S. Bureau of Mines, and other groups, and will be considered the official source of drilling information by the U. S. Department of the Interior.

Many of the wells drilled in southeastern Kansas are not presently scouted. Because of this the CSD District 12 Chairman is sending this Well Completion Report form to all operators who have stated their intent to drill a well. The information received will also be placed on open file in the Oil and Gas Division offices of the State Geological Survey of Kansas. The cooperation of all of the operators in returning the completed form will be greatly appreciated.

:--WELL LOG--:

2-28-23 E

Farm: Ester Holtman # 23
Operator: Wel-Kan Oil Co.
Contractor: A.H. Alcock Drlg. Co.
Comm: 6-14-1965
Comp: 6-24-1965
Prod: (OIL)

Location: E/2, NE/4, Sec. 2, T. 28 S., R. 23 E.
Crawford County Kansas.

:--Casing Record--:

Size	Put in	Pulled	Left in
8	8	8	
6-5/8	36		36
4-1/2	140		140

2	Soil	2
18	Clay	20
30	Shale	50
4	Lime (Pawnee)	54
4	Shale	58
36	Lime (Pawnee)	94
12	Shale (Dk)	106
1	Lime	107
14	Shale (Dk)	121
15	Shale (Lt, Sdy)	136
5.6	" " " L.S.O.	141.6
3	" " " Better	144.6 S.I.M.

:--CORE REPORT--:

144.6-148.3	Sand	Good
148.3-152.2	"	"
152.2-156.7	"	"
156.7-161	"	Fair
161. -165.6	"	"
(Last 12" Barren)		
165.6	T.D.	

-12 feet Sand

Shot with 18 Qts. Nitro., (Grove Torpedo Co.)

Top Of Shot 142'

Bot of Shot 161

Shot Packed in, Packing held for 5 Minutes, then Shot broke through, and came out Gradually.

165' 2" Tubeing (Used) set 6" off Bottom. 5' Anchor

160' 7/8" Rods (Used)

4' Brass Working Bbl.

2 New Valves (Upper, & Lower)

Well put on the Jack 6-25-1965

AHA.

A.H. Alcock