

Well Log

3-28-23E

Mein Farm No I
E.J. Dunigan Operator
A.H. Alcock Contractor
Completed 7-7-61
Production in Peru

Location NE 1/4 Sec 3
28s 23e Crawford County

Soil	2	
Clay	9	
Lime	14	
Shale	16	
Lime	26	
Shale Sandy Fresh Water	66	
Lime	68	
Shale	69	
Lime	70	
Shale	93	
Lime (Pawnee)	97	
Shale	101	
Lime (Pawnee)	133	Good Show Oil in Pawnee
Shale	145	III To II5
Lime	147	
Shale	189	
Sand (Peru) Good show Oil	204	
Shale	209	
Lime (Oswego)	227	Fractured Peru 5000 Lbs
Shale	232	sand 120 barrels Oil
Lime (Oswego)	239	Formation broke 800 lbs
Shale Little Water	244	took fluid and sand 450
Lime (Oswego)	246	Fract in 16 feet open hole.
Shale	340	
Lime	343	
Shale	400	
Sand Bartlesville (Dry)	408	
Shale	515	
Sand Tucker (Dry)	570	
Shale	624	
Chert Miss Lime	635	
Lime & Dolomite	652	Total Depth

Well Plugged back to bottom of Peru and Now producing in Peru

3- 28- 23 E

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- E. J. DUNIGAN
Farm- Main

No. 1

SEC. 3 T. 28 R. 23E
NE NE SE

Total Depth. 652'

Comm. 6-28-61


Comp. 7-7-61

Shot or Treated.

Contractor. A. H. Alcock

Issued. 12-23-61

County Crawford
KANSAS



CASING:
no casing record

Elevation. ??

Production. Oil

Figures Indicate Bottom of Formations.

soil	2
clay	9
lime	14
shale	16
lime	26
shale sandy fresh water	66
lime	68
shale	69
lime	70
shale	93
lime (Pawnee)	97
shale	101
lime (Pawnee)	133
good show oil in Pawnee 111-115'	
shale	145
lime	147
shale	189
sand (Peru) good show oil	204
shale	209
lime (Oswego)	227
shale	232
lime (Oswego)	239
shale little water	244
lime (Oswego)	246
shale	340
lime	343
shale	400
sand Bartlesville (Dry)	408
shale	545
sand Tucker (dry)	570
shale	624
chert Miss. lime	635
lime & dolomite	652
Total Depth	

Well plugged back to bottom of Peru and
now producing in Peru.

Fractured Peru 5000 lbs.
sand 120 barrels oil
Formation broke 800 lbs
took fluid and sand 450