



copy

	FT.	IN.
Grey sandstone	3	
Dark slate	2	10
" " hard	1	
Black slate, soft tary		6
Coal	1	4
Drab clay	1	10
Grey sandstone (251-1/4 ft.)	2	9
" "	3	2
Light grey sandy shale	4	10
Grey shale	4	10
Brown slate	2	10
Coal		3
Dark grey shale	4	
White sandstone		7
Grey sandstone	1	10
" " hard		4
stone		9
Brown slate (281 ft. 11 in.)	1	
Limestone		3/1/2
Grey shale	3	3
Dark shale	4	1
Black slate	1	5
Parities		1-1/2
Black slate		5
Parities		5
Black slate	6	5-1/2
Coal		10
Clay	1	4
Light grey gritty shale	2-	1
" " " mineral	2	3
Grey sandstone	1	
Dark shale (307 - 2)		6
Coal		2-1/2
Dark grey gritty shale	1	11
Grey slate		5-1/2
Black slate	1	6
Light drab shale	2	2
" grey "	6	6
L. stone	1	1-1/2
Grey slate		8
Coal		0-1/2
Grey shale hard	11	4
Grey slate	1	6
C		3
Dark grey shale	6	9
Grey slate	3	3
Coal		5
Light shale	4	5
Dark shale	3	5
Dark slaty shale	3	3
Darker slaty shale		9
Coal	1	3
Clay		1/2
Coal		2
Grey gritty shale	1	8-1/2
Light grey gritty shale	1	5
Dark and hard shale (369)	2	9
Light grey shale	2	6-1/2
Dark " "	6	0-3/2

~~copy~~

Gritty grey shale  
 Light grey hard  
 Light grey shale  
 Light grey hard shale  
 " " hard (395)  
 Grey shale hard  
 " " " (401)  
 Drill one ft. 7 in. after we struck gas.

FT.	IN.
6	6-1/2
4	7
7	
5	10
1	
4	5
1	7

28<sup>s</sup>-(23<sup>e</sup>)#24<sup>e</sup>

copy

FULLER & RANDOLPH  
ATTORNEYS AT LAW  
GIRARD, KANSAS

Girard, Kas. March 23rd, 1899.

N. H. Darton, Esq.,

Washington, D. C.

Dear Sir:-

Your letter of 15th inst addressed to R. H. McKay asking him for a report of all deep wells and borings in this vicinity, has been handed me for reply, and concerning the matter will say that during the month of January, 1898, a company was formed at this place for the purpose of prospecting for natural gas in the North Western part of this county, which caused three wells to be drilled something over 400 feet in depth as follows: Lundrigan well, 2 miles West of Farlington, Crawford, county, Kansas, a report of which I herewith enclose. Herlocker well about 1-1/2 miles South and 1 mile East of Farlington, a report of which I herewith enclose. I also enclose report of well designated as the Gardner well, drilled some time Before that which is designated as the Herlocker well, which is located 3-1/2 miles North of the city.

There was one other well drilled by the gas company about 2 miles West of the Herlocker well, I can give you no report as to the water in these borings for the reason that no attention was paid to it except to get it out of the way of the drill.

In the city of Girard there have been two deep wells bored. I cannot give you a statement of the drilling or substance bored through, but they are between 800 and 900 feet deep, were bored for water and the water stands within 175 feet of the surface. The city of Girard is supplied by one of these wells with water. With the use of the best pumps obtainable the water is not perceptibly lowered any season of the year.

Trusting this information may be of some use to you, I remain.,

Yours, truly, *[Signature]*

# Kansas Memory



KANSAS HISTORICAL SOCIETY

## Plat book, Crawford County, Kansas - 8

(1906)



