

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY GATY & GRAHAM

SEC. 5 T. 28 R. 3E

FARM Graham "A"

NO. 2

LOC. SW NW SE

TOTAL DEPTH 3155

COMM. 4-6-51


COMP. 4-16-51

SHOT OR TREATED

CONTRACTOR Morrison Drlg. Co., Inc.

ISSUED 5-19-51

COUNTY Butler



CASING

No casing record.

ELEVATION 1317

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

cement	65	cem. sand- green gry wht	
shale & lime	215	sand filled shale	3109½
lime & shells	335	gry lime	3112
lime	390	solid green shale sand in	
shale & lime	485	green shale-cem. sand	
shale & shells	570		3121
lime & shale brks	715	cem. sand	3136½
shale & shells	1010	sand & oolitic lime wht	
shale & lime	1250	& gry arbuckle top	3138½
shale & shells	1320	lime, wht tan gry & chert,	
shale, sandy	1380	some free oil HFW	3148½
lime w/shale strks	1450	lime	3155
shale	1560	Total Depth	
lime & shale strks	1600		
lime	1680	Scout Tops:	
shale & lime	1750	Kansas City	2345
shale & shells	1930	Simpson	3061
lime & shale strks	2040	Arbuckle	3145
shale	2120		
sand	2130		
lime & shale	2170		
lime & shale brks	2190		
shale & shells	2315		
shale	2350		
lime K.C.	2460		
shale & lime	2500		
lime & shale strks	2630		
lime & shale	2680		
shale & shells	2707		
shale	2840		
lime & chert	2875		
lime	2963		
shale	2995		
lime	3004		
shale & lime	3059		
shale	3061	RTD	
blk shale	3064½		
sand w/some blk shale			
stain in sand	3069		
hrd cem. sand some stain			
some free oil	3080		
brown sandy lime, large			
imbedded sand grains	3082½		
wht dolomite with glauconite			
some green & gry shale	3089		
same plus pyrite	3092		
brown shale & hrd wht			
cem. sand w/glauconite	3095		
hrd sand, green shale			
w/imbedded sand, brown			
shale	3101		