


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas

Company - Talbott & Sohio
Farm - Barnhart No. 3

SEC. 23 T. 26S R. 3E
NW SW NE

Total Depth. 2996½'
Comm. 6-7-49 Comp. 6-19-49
Shot or Treated.
Contractor. Penguin Pet., Inc.
Issued. 9-3-49

County. Butler
KANSAS



Elevation. 1318

Production. 50 BOPD

CASING:

8-5/8" @ 168.73'
5-1/2" @ 2959.52'

Figures Indicate Bottom of Formations.

lime	40
shale & lime shells	120
sand	132
shale & shells	145
lime	165
lime broken	315
red rock	330
sand	340
broken lime	410
shale & lime	700
shale	835
sandy shale	990
sand	1005
shale & shells	1400
broken lime	1450
shale & lime	1780
shale	1895
broken lime	1945
lime	2080
lime & shale	2125
lime	2365
lime & shale	2415
shale	2455
lime	2502
lime & shale	2762
lime	2805
lime & shale	2885
lime	2888
shale	2960 R.T.D.
shale	2981
sand	2996½

1st free oil 2986-88½
2 BOPH @ 2996½

TOPS:

K. C. limestone	2305
Mississippian	2755
Kinderhook	2888
Simpson sandstone	2981