

36-28-16E

COPY

JAMES GUINOTTE  
PETROLEUM GEOLOGIST  
January 15, 1965

P. O. Box 2  
CHANUTE, KANSAS  
OFFICE  
9 1/2 EAST MAIN

PHONES  
OFFICE HE 1-4130  
RES. HE 1-4028

Wm. Farish III

Folger Well #2-A

Comm. Drlg: Jan. 13, 1965  
Comp. Drlg: Jan. 15, 1965

Location: SE SE SE NW  
Section 36-28S-16E  
Wilson County, Kansas

Casing: 8 5/8" @ 20'

Elevation: 867 Gd

Samples by J.E. Guinotte

SAMPLES

Oswego ls - 619

600 - 610 - Gray shale sdy - slight odor - no oil stain

CORE #1 - 610 - 625  
Recovered 15 feet

- 610 - 618 - Gray shale
- 618 - 619 - Coal & watery green shale
- 619 - 625 - Gray xlyn dense lime
- Spotted oil stains - 621 - 621.3

- 620 - 630 - Black shale & gray/tan xlyn ls
- 630 - 640 - Tan xlyn dense & black shale
- 640 - 650 - Black & gray shale
- 650 - 660 - Gray & green sdy shale
- 660 - 664.5 - Green sdy shale - slight odor - no stain

January 15, 1965

" CAT WALK DESCRIPTION "

CORE #2 - 664.5 - 689.5  
Recovered 23.5 feet

- 664.5 - 668.5 - Gray-green watery shale
- 668.5 - 669.3 - Gray brk sdy shale - slight oil stain  
sand lense fine grd - brown - bleeding  
oil and gas
- 669.3 - 671.7 - Gray brk sdy shale - laminated micaceous  
96% shale - sd lense brown fine grd  
bleeding oil and gas - spotted
- 671.7 - 673 - Gray sdy lime - tight & dense - no stain -  
no free oil
- 673 - 675 - Brown fine grd micaceous sd - fair porosity  
bleeding oil & gas

Wm. Farish III

Folger Well #2-A

- 675 - 677 - Black carbonaceous sd - fair/gd porosity  
bleeding oil & gas - slight water
- 677 - 680 - Brk sdy shale & sd - fine grd - micaceous  
sd lenses - bleeding oil & gas - 75% shale
- 680 - 684 - Brk sdy shale & shale - 95% shale sand  
laminations - bleeding oil & gas
- 684 - 688 - Gray shale
- 688 - 689.5- Loss

- Squirrel sand - 673 - 675 = 2'
- Black sand - 675 - 677 = 2'
- Broken sand - 677 - 680 = 3'


Core picked up by Oilfield Research for analyses.

DRILLING & SAMPLE TOPS

Base Kansas City ls	341	
Top Oswego ls	619	
Squirrel sand	673 - 677	4'
Broken sand	677 - 680	3'

T.D. 689.5

Recommended that #2-A Folger be plugged and abandoned.

  
 James E. Guinotte

JEG/v1