

2-28-4E

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- H & M DRILLING CO.  
Farm- Ambler No. 8

SEC. 2 T. 28 R. 4E  
NE SE NW

Total Depth. 2655'  
Comm. 3-11-54 Comp. 3-17-54  
Shot or Treated.  
Contractor.  
Issued. 7-24-54

County Butler

KANSAS



Elevation. 1295'

Production. Est. 30 Bbls.

- CASING:  
8 5/8" - 68' w/50 sx cem.  
5 1/2" 2634 w/40 sx cem.

Figures Indicate Bottom of Formations.

|                 |          |
|-----------------|----------|
| surface soil    | 10       |
| lime-shale      | 300      |
| shale-shells    | 350      |
| lime-shale      | 545      |
| shale-shells    | 1150     |
| lime-shale      | 1555     |
| shale-sdy shale | 1750     |
| lime            | 1880     |
| lime-shale      | 1980     |
| shale           | 2082     |
| lime            | 2260     |
| lime-shale      | 2275     |
| shale           | 2310     |
| lime            | 2390     |
| lime-shale      | 2520     |
| shale-red rock  | 2568     |
| shaley sand     | 2636     |
| sand            | 2638 RTD |
| Lime            | 2655     |
| Total Depth     |          |

|             |      |
|-------------|------|
| TOPS: Scout |      |
| Kansas City | 2052 |
| Simpson     | 2565 |
| Arbuckle    | 2622 |

Lane Wells shot 9 shots  
@ 2600-2603  
Shot 9 shots from 2626-2629

No fluid

Shot from 2610-2615

Making about 10 Bbls. an hr.  
w/very little oil.