

SEP 26 1972

15-28-6E

**KANSAS DRILLERS LOG**


API No. 15 — 015 — 20,532 *State Geological Survey*  
 County Number **WICHITA, BRANCH**

S. 15 T. 28S R. 6 E ~~XX~~

Loc. SW NE NE

County BUTLER

640 Acres  
N



Locate well correctly

Elev.: Gr. 1324

DF 1326 KB 1329

Operator  
**REX & MORRIS DRILLING COMPANY, ET AL**

Address  
**P. O. BOX 334, EL DORADO, KANSAS 67042**

Well No. 3 Lease Name DUNN

Footage Location  
990 feet from (N) line 990 feet from (E) line

Principal Contractor **TRIANGLE DRILLING CO.** Geologist **JOSEPH E. MORKLAND, JR.**

Spud Date **30 AUGUST 1972** Total Depth **2995' KB** P.B.T.D. - -

Date Completed **7 SEPTEMBER 1972** Oil Purchaser **NONE**

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE CASING	12 1/4"	8 5/8"	28#	219' KB	COMMON	150	3% CALCIUM CHLORIDE

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
NONE					

**TUBING RECORD**

Size	Setting depth	Packer set at
NONE		

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
NONE	

**INITIAL PRODUCTION**

Date of first production <b>NONE</b>	Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **REX & MORRIS DRILLING COMPANY, ET AL** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. **3** Lease Name **DUNN** DRY HOLE

S **15** T **28S** R **6** E SW NE NE


**WELL LOG**  
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
ALL MEASUREMENTS ARE FROM ROTARY BUSHING			ADMIRE SH	375
			BURLINGAME LS	680
SURFACE HOLE	0	219	B/BURLINGAME	765
			HOWARD LS	875
SAND	0	15	TOPEKA LS	1010
LIME	15	85	OREAD LS	1340
LIME & SHALE	85	215	HEEBNER SH	1385
LIME	215	219	DOUGLAS SH	1830
LIME & SHALE	219	455	BROWN LS	1610
SHALE & LIME	455	835	LANSING LS	1680
LIME	835	1020	KANSAS CITY LS	2005
LIME & SHALE	1020	1340	B/KC LS	2192
SHALE & LIME	1340	1610	LENAPAH LS	2262
BROWN LIME	1610	1645	PAWNEE LS	2311
SHALE	1645	1680	FORT SCOTT LS	2378
LANSING LIME	1680	1950	CHEROKEE SH	2438
SHALE	1950	2005	ARDMORE LS	2513
KANSAS CITY LIME	2005	2192	MISSISSIPPI LS	2644
SHALE	2192	2262	COWLEY	2672
LIME	2262	2268	OSAGE	2727
LIME & SHALE	2268	2644	KINDERHOOK SH	2914
MISSISSIPPI LIME	2644	2914	MISNER VIOLA	2992
KINDERHOOK SHALE	2914	2992	RTD & TD	2995
VIOLA LIME	2992	2995		
ROTARY TOTAL DEPTH	2992	2995		

DST # 1: 2984' - 2995' MISNER SANDSTONE  
 OPEN 1 1/2 HR., STRONG BLOW DECREASING TO FAIR BLOW. RECOVERED 40° OIL, 1080° SLIGHTLY OIL CUT SULFUR WATER (5% OIL) AND 840° SULFUR WATER. IBHP 1100#, IFP 60#, FFP 893#, FBHP 1100#, ALL IN 30 MINUTES.

PLUGGED HOLE - DRILLING MUD TO 225', SET PLUG & 1/2 SACK HULLS & CEMENTED WITH 20 SACKS CEMENT. FILLED WITH MUD TO 40', SET PLUG & 1/2 SACK HULLS AND CEMENTED WITH 10 SACKS CEMENT. PUT 2 SACKS CEMENT IN RAT HOLE.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



*[Signature]*  
 Signature  
 OFFICE MANAGER  
 Title  
 21 SEPTEMBER 1972  
 Date