


WELL RECORD

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)

API# 15-015-20,504



Lease Name: DUNN Well No. 1
 Well Located: NE NE NE
SEC 15 TWP 28S RGE 6 EAST
 Operator: REX & MORRIS DRILLING COMPANY
 Address: P. O. BOX 334, EL DORADO, KANSAS 67042
 Elevation: Ground 1332 D.F. 1334 K.B. 1337
 Type Well: (Oil, gas, dry hole) OIL WELL

Drilling Commenced: 26 MARCH 1972 Drilling Completed: 4 APRIL 1972
 Well Completed: 13 APRIL 1972 Total Depth: 2992' RB
 Initial Production: 35 BOFD

Casing Record

Size: 8 5/8" OD Set at 204' RB Size: Set at
 Size: 5 1/2" OD Set at 2990' RB Size: Set at

Liner Record

Size: NONE Set from To

Cementing

Casing Size	Sacks	Type Cement and Additives
<u>8 5/8" OD</u>	<u>135</u>	<u>COMMON CEMENT W/3% CALCIUM CHLORIDE</u>
<u>5 1/2" OD</u>	<u>175</u>	<u>COMMON CEMENT - CEMENT TOP 2520'</u>

Perforations

Formation	Perforated Interval and Number Shots
<u>NONE</u>	<u>OPEN HOLE</u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>

Electric Log Run (Show type log and depths covered)

JENKINS WIRELINE SERVICES - GAMMA RAY - NEUTRON SURFACE TO 2991' RB

ALL MEASUREMENTS FROM ROTARY BUSHING
WHICH IS 5' ABOVE GROUND LEVEL

R. T. D. & T. D.

DST # 1: 2267 - 2343 - WAYSIDE SAND, PERU SAND
OPEN 1 HOUR, WEAK BLOW. RECOVERED 62' VERY
SLIGHTLY OIL CUT MUD. IHP 85% IN 30 MIN.
SUPER-CHARGED. FLOW PRESSURES 17# TO 34#.
IHP 550# IN 30 MINUTES.

DST # 2: 2736 - 2760 - MISSISSIPPIAN OSAGE
OPEN 1 HOUR, WEAK BLOW FOR 30 MINUTES, RECOVERED
10' OIL SPECKLED MUD. IHP 30% IN 30 MINUTES,
FLOW PRESSURES 95# TO 15#, IHP 95# IN 30 MINUTES.

DST # 3: 2979 - 2992 - MISNER - VIOLA
OPEN 1 1/2 HOURS, STRONG BLOW, RECOVERED 580' CLEAN
GASSY OIL PLUS 190' GASSY, MUDDY OIL, GRAVITY 35.7.
IHP 1048# IN 30 MINUTES, FLOW PRESSURES 137# TO
292#, IHP 1048# IN 30 MINUTES.

COMPLETION

R.U.S.T. DRILLED CEMENT & CLEANED HOLE TO T.D.
BAILED HOLE CLEAN & SWABBED DOWN. 2550' FILL UP
IN 15 HOURS. NO WATER. SWABBED DOWN & TESTED.
2660' FILL UP IN 16 HOURS, NO WATER. P. O. P.

LOG TOPS

TOP
HEEB
TARK
DOUG SH
BN IM
IANS
KC
BKC
LEN
CHER
CATT SD
BART SD
MISS DOL
KIND
MISN-VIOLA
TD
2992
2990
2913
2659
2631
2572
2439
2260
2192
2005
1681
1612
1435
1410
1388
1012

Formation	Top	Bottom
SURFACE HOLE	0	204
LIME	204	350
LIME & SHALE	350	1113
LIME	1113	1270
LIME & SHALE	1270	1680
LANSING LIME	1680	1855
LIME & SHALE	1855	2003
KANSAS CITY LIME	2003	2190
LIME & SHALE	2190	2632
BARTLESVILLE SAND	2632	2640
LIME & SHALE	2640	2660
MISSISSIPPI	2660	2912
SHALE	2912	2990
TOIA MISNER	2990	2992

