


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg., Wichita, Kansas

REX & MORRIS ET AL.
De Moss No. 6 -A

SEC. 8 T. 28 R. 7E.
NE NW NW

Total Depth. 2684
Comm. 5-29-40 Comp. 7-9-40
Shot or Treated. 110 qts.
Contractor. Rex & Morris Drlg. Co.
Issued. 9-7-40

County Butler.



CASING.

15 1/2" 122 All Pulled.
12 1/2" 771' All Pulled.
10" 1620' All Pulled.
8 3/4" 2139' All Pulled.
7" 2640' Left In.

Elevation.

Production. 75 B.

Figures Indicate Bottom of Formations.

cellar & red rock	25	lime	940	lime hard	2080
gravel	30	shale	945	lime	2112
gravel & clay	40	lime	950	HFW 2095	
lime & shale	60	shale	1025	lime	2135
shale	70	lime	1050	shale	2139
red rock	85	shale	1055	lime	2145
shale	125	lime	1060	shale blk	2150
lime	155	shale	1065	lime	2165
shale	165	lime	1095	shale	2170
lime	175	shale	1110	lime	2190
shale	180	lime	1120	smell oil 2170-75	
lime broken	220	shale	1130	shale	2280
1/2 BW 210		lime	1140	lime	2285
shale	225	shale	1145	shale	2300
red rock	235	lime	1155	lime	2310
lime	270	shale	1160	shale	2335
shale	280	lime	1175	Caving.	
lime	290	shale	1185	red rock	2340
shale	295	lime	1195	shale	2345
lime and shale	335	shale	1200	lime	2355
shale and shells	365	lime	1205	Caving.	
shale	375	shale	1240	shale	2400
lime	395	hole caving 1215-1240		lime sdy	2425
lime broken	415	lime	1255	lime	2465
shale	425	shale	1275	1/2 BWPH 2425-40	
lime	430	lime	1280	shale	2525
shale	525	shale	1290	lime broken	2535
sand	545	lime	1295	shale	2545
14 BWPHR 525-545		shale	1335	lime	2552
shale	600	lime	1380	shale	2560
lime	610	shale	1405	lime	2565
sand	625	lime broken	1425	shale	2615
shale	690	shale	1455	shale sdy	2640
Carrying 17 BWPH 670		lime	1460	sand	2660
lime	695	shale sdy	1535	sand	2684
shale	700	2 1/2 BWPH 1495-1505		1st oil 2660	
lime	710	Total 4 1/2 BWPH		Total Depth.	2684
shale	735	2 BWPHR 1530-1535			
lime	768	Total 6 1/2 BWPH			
more water 755-60		shale	1618		
shale	775	lime	1640		
lime	780	shale	1700		
shale sdy	840	lime	1875		
2 BW 820		1/2 BW 1730			
shale & shells	860	2 1/2 BWPH 1760-70			
shale	890	Total 3 BWPH			
shale & shells	905	shale	1930		
lime	910	shale sdy	1975		
shale	915	shale	2018		
lime	925	lime	2055		
shale	930	Good show oil 2027-33			