

REX AND MORRIS ET AL.
Farner No. 1.


SEC. 8 T. 28 R. 7 E.
NE SW NW

Total Depth. 2672
Comm. 8-26-38 Comp. 9-30-38
Shot or Treated. 120 qts 2646
Contractor. Rex and Morris Drlg. Co.
Issued. 2-11-39

County Butler.

CASING.

12 1/2" 747'
10" 1556'
8 1/4" 2118'
6 5/8" 2636'



Elevation.

Production. 40 B.

Figures Indicate Bottom of Formations.

soil	25	lime	820	lime	1450
shale	35	shale	860	shale	1460
lime	40	shale shells	870	sand	1475
red rock	60	lime	880	sand broken	1505
lime	70	shale	885	10 BWPFR 1460-1515	
5 BWPFR 60-70		lime	890	lime	1610
shale	75	shale	895	shale	1665
lime	85	lime	905	lime	1670
shale shells	95	shale	915	shale	1680
lime	105	lime	920	lime	1850
shale	110	shale	925	1 1/2 BW 1680-1700	
lime	125	lime	930	1 1/2 BWFH 1750-55	
shale	130	shale	980	shale	2000
lime	150	lime	985	lime	2113
shale	160	shale	995	HFW 2075-85	
lime	195	lime	1015	shale	2115
1 BWPFR 160-95		shale	1020	lime	2120
shale	215	lime	1025	shale	2125
lime	250	shale	1035	lime	2142
lime broken	260	lime	1070	shale	2146
shale	265	shale	1075	lime	2160
lime	270	lime	1080	lime sdy	2170
shale	275	shale	1085	sdv shale	2180
lime	285	lime	1105	shale	2275
shale	290	shale shells	1135	lime	2285
lime	300	lime	1145	shale	2325
shale	315	shale	1150	lime cave	2340
lime	320	lime	1170	shale	2390
shale	335	1 BWPFR 1150-70		lime	2395
shale&shells	350	shale	1180	lime broken	2425
lime	365	lime broken	1185	lime	2450
shale&shells	390	lime	1200	shale	2550
shale	455	shale shells	1210	lime shells	2555
lime	460	shale	1230	shale sdy	2600
shale	485	lime	1235	shale sdy shale	2632
lime	490	shale	1240	sand shaly	2633
shale	525	lime	1250	sand	2648
lime	530	shale	1265	show oil.	
shale	575	cave		sand	2659
sand	600	lime	1270	Black Mica in	
10 BWPFR 575-600		shale	1280	bedding 2648-55	
shale	625	lime	1285	sand blk mica	2668
lime	630	shale	1305	sand clean	2672 Total Depth.
shale	635	lime	1315	10' Oil in 6" bailer in 1 hr.	
lime	640	shale	1330		
shale	660	lime	1350		
lime	685	shale	1365		
shale	705	sand	1375		
lime broken	720	4 BWPFR 1365-75			
lime	744	shale	1380		
shale	765	lime	1400		
red rock	770	shale	1415		
shale	790	lime	1420		
sand	800	shale	1425		
1 BWPFR 790-800		lime	1430		
shale	815	shale	1445		