


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.

ADAIR-MORTON
Brandt No. 11

SEC. 15 T. 28 R. 7E
NW NE NE

Total Depth, 2763
Comm. 5-29-40 Comp. 6-26-40
Shot or Treated.
Contractor.
Issued. 8-31-40

County Butler.



CASING.

12 1/2" 865'
10" 1560'
8 3/4" 2180'
5 3/16" 2734'

Elevation.

Production. 296 B.

Figures Indicate Bottom of Formations.

cellar & clay	10	shale	1035	Hardened up 2762.
gravel	15	lime	1065	
clay	20	shale	1080	show oil 2120-25
gravel	25	lime	1085	small sh oil 2725-28
shale	30	shale	1090	no Inc. oil 2728-30
lime	50	lime	1140	Inc. Oil 2733-34
shale	55	shale	1145	
red rock	65	lime	1150	1/2 BW 190'
shale and shells	85	shale shells	1175	6 BW 725-30'
lime	95	shale	1195	2 1/2 BW 1480-90'
shale	100	lime	1215	1/2 BW 1710'
lime	115	shale	1240	HFW 2100'
shale	125	shale lime shells	1290	
lime	130	shale	1305	
shale	135	lime broken	1345	
lime	150	shale	1360	Tops.
shale	165	lime	1365	K.C. 1999
lime	200	shale	1385	Miss 2724
shale	210	lime	1400	
red rock	215	shale	1425	
lime	255	lime	1430	
shale	270	shale	1450	
lime	275	shale	1470	
shale	290	shale broken, no water	1470	
lime	295	limo	1475	
shale	320	shale	1480	
lime	330	sand	1490	
shale	335	shale	1555	
lime	345	shale	1590	
shale shells	355	lime	1615	
shale lime shells	380	shale	1672	
shale	420	lime	1845	
lime	425	shale	1990	
shale	445	lime	2165	
red rock	455	sand broken	2175	
shale	465	shale	2260	
red rock	470	lime	2265	
shale	490	shale	2280	
lime	495	lime	2290	
shale	620	shale	2315	
lime shells & shale	640	shale pink	2320	
lime	645	shale	2325	
shale	660	lime	2340	
lime	665	shale	2390	
shale	670	shale shells	2410	
lime	680	lime	2420	
shale	700	shale	2435	
lime	740	lime	2450	
shale	745	shale	2455	
lime	750	shale shells	2500	
shale	862	shale lime shells	2545	
lime	885	shale	2640	
shale	890	shale sdy	2685	
lime	900	shale	2724	
shale shells	915	lime	2733	
shale	990	dolomite & lime	2734	
lime	1015	lime OIL PAY	2743	
		lime	2750	
		dolomite Sat.	2763	Total Depth.