

REX AND MORRIS ET AL.  
Whitmer No. 1.


SEC. 16 T. 28 R. 7E.  
NW SE SE

Total Depth. 2687'  
Comm. 8-20-40 Comp. 9-27-40  
Shot or Treated. 2000 gal acid.  
Contractor, Rex and Morris Drlg. Co.  
Issued. 1-11-41

County Butler.

CASING.

20" 18' Left In.  
15 1/2" 73' All Pulled.  
12 1/2" 699' " "  
10" 1425' UR 1477 All Pulled.  
8 1/4" 2375' All Pulled.  
7" OD 2665' Left In. cemented.



Elevation.

Production. Pot. 557 B.

Figures Indicate Bottom of Formations.

red mud	14	lime	1020	lime	2205
gravel	18	shale	1025	shale	2230
lime	48	lime	1030	lime	2240
2 1/2 BWPB 48'		shale	1040	hole caving.	2235
shale dark	50	lime	1055	shale light	2250
lime	65	shale	1060	shale red	2255
shale and lime	110	lime	1080	shale shells	2305
lime	135	shale	1085	shale	2310
red rock	140	lime	1120	lime	2315
shale blue	145	shale cave 1130	1130	shale	2335
lime	180	lime	1155	lime	2345
1 BWPB 145-60		shale	1180	lime sdy	2365
shale	190	lime	1190	lime white	2370
shale dark	205	shale	1245	lime and shale	2375
red rock	210	lime	1260	HFW 2365-75	
lime white	215	lime white	1280	lime dark blue	2390
shale white	250	shale dark	1283	lime shale brks	2425
shale dark	260	lime shell	1285	lime	2440
lime and shale	305	shale dark	1290	shale	2455
lime	315	shale and shells	1310	lime	2460
shale	330	red rock	1315	lime shell	2480
red rock	335	lime	1320	lime shale dark	2515
shale shells	375	red rock	1325	shale light	2530
shale dark	380	lime	1350	shale and shells	2550
red rock	390	shells shale	1380	shale	2592
shale dark	410	shale light blue	1395	lime	2596
red rock	415	sand 2 BWPB 1405	1425	shale	2635
shale dark	435	HFW 1425		shale light	2663
shale	515	shale	1440	lime	2676
lime	520	lime sdy	1445	show oil	2665-2676
shale	525	shale	1454	brown dolomitic lime	
shale sdy	540	lime	1460	oil pay	2676-2684
4 BWPB 525-540		shale	1465	First free oil	2676-80
shale	545	sand	1471	Tested 1 hr at	2684-2 1/2 BO
shale dark	605	shale	1540	blk dolomitic lime	
lime and shale	630	lime shells	1550	no increase	2684-2687
lime broken	660	lime	1580		
lime	685	shale	1685 ?	Total Depth.	
shale	690	lime	1795		
lime	695	1 BWPB 1640-45 6 BWPB 1680-85			
shale	745	carrying 7 BWPB.			
lime	750	shale	1830		
shale	785	lime	1835		
shale light	800	shale	1855		
limelight	820	lime	1865		
shale dark	830	shale	1935		
lime	840	lime	2055		
shale	845	2 BWPB 2040-2045			
lime	855	shale dark	2058		
shale	930	lime	2085		
lime	950	shale blk	2087		
shale	970	lime	2120		
lime	1005	shale sdy	2135		
shale	1010	shale	2200		