

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
Wichita, Kansas 67217

Rev. 3-15-72
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1974
CONSERVATION DIVISION
Wichita, Kansas

Lease Owner Midwest Supply Company

Address 343 Marmaton Rd. El Dorado, Ks 67042

Lease (Farm Name) Farrell SWD

Well No. 3

SW SE SE SW 82' N & 412' W of
Well Location SE Corner of SW/4 Sec. 21 Twp. 28 Rge. 8 (E) E (W)

County Butler

Total Depth 3520

Field Name

Oil Well Gas Well Input Well SWD Well XX Rotary D & A

Well Log filed with application as required Yes

Date and hour plugging is desired to begin As soon as rig becomes available

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Charles V. Cross

Address Box 1020, El Dorado, Ks 67042

Plugging Contractor THE BUCKEYE CORPORATION

License No. 687

Address Box 1020, El Dorado, Kansas 67042


Invoice covering assessment for plugging this well should be sent to:

Name Midwest Supply Company

Address 343 Marmaton Rd., El Dorado, Ks 67042

and payment will be guaranteed by applicant or acting agent.

PLEASE SEND PERMIT TO PLUG TO
THE BUCKEYE CORPORATION
BOX 1020
EL DORADO, KS 67042
RATHER THAN THE LEASE OWNER.

Signed: 
Applicant or Acting Agent

Date: December 16, 1974

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

December 17, 1974

WELL PLUGGING AUTHORITY

Well No.	3
Lease	Farrell SWD
Description	SW SE SE SW 21-28-8E
County	Butler
Total Depth	3520
Plugging Contractor	Budkeye


Midwest Supply Company
343 Marmaton Rd
El Dorado, Kansas 67042

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Ted Dewey, Box 336, Augusta, Kansas 67010
is hereby assigned to supervise the plugging of the above named well.

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock

Administrator

P. O. Box 17027

Wichita, Kansas 67217

Well Plugging Authority: Dec.17/74

Well Plugging Completed: Dec.21/74

Operator's Full Name midwest Supply Co.

Complete Address 343 Marmaton Rd. El Dorado, Kans. 67042

Lease Name Farrell Well No. 3

Location SW SE SE SW AUB KC Sec. 21 Twp. 28 Rge 8E (E) (W)

County Butler Total Depth 3520'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Buckeye Corp.

Address 605 S. Main El Dorado, Kans. 67042 License No. 687

Operation Completed: Hour Day 21 Month Dec. Year 1974

The above well was plugged as follows:

T.D. - 3520'. PB @ 3968'

2718' - 7" cemented

2550' - 5 1/2" liner 2550' - 3020'

Packer with tubing 2970'

Pulled 72 joints tubing

Dumped 5 sacks cement on tubing stub

7" pulled in two @ 110'

Bridge @ 110', 10 yds. Redi-mix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/24/74

INV. NO. 7942-E

Signed: Paul E. Densley
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1974
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

TABLE MESA OIL CO.
Farrell No. 3


SEC. 21 T. 28 R. 8E.
Sec SW

Total Depth. 3008 P.B. 2752
Comm. 6-17-40 Comp. 9-18-40
Shot or Treated.
Contractor.
Issued. 10-12-40

County Butler.
RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1974

CONSERVATION DIVISION
Wichita, Kansas



CASING.

12 1/2" 691' 8 1/2" 1787
UR 815' UR 2115'
10" 1455' 65/8" 2718' cemented. Elevation.
UR 1480'

Production. 20 B.

Figures Indicate Bottom of Formations.

soil	15	lime	830	shale	1950
lime	30	shale	835	lime	1955
red rock	35	lime	840	shale	2000
lime	60	shale	845	lime	2045
shale	63	lime	855	4 BW 2015	
lime	70	shale	860	sand	2050
shale	80	lime	870	HFW 2045	
lime	95	shale	925	lime	2085
shale	105	lime	935	shale	2090
lime	120	shale	945	lime	2155
shale	125	lime	975	shale	2300
lime	133	shale	980	lime	2325
shale	150	lime	1010	shale	2365
lime	155	shale	1015	lime	2425
shale	185	lime	1035	shale	2691
lime	225	shale	1040	lime	2705
shale	245	lime	1060	chat	2718
lime	268	shale	1065	show oil 2705-2707	
shale	295	lime	1110	lime	2945
lime	310	shale	1150	show oil 2736-38	
shale	320	lime	1180	SL corr. 2762 to 2778	
lime	325	shale	1190	1 1/2 BW 2785-2795	
shale	330	lime	1200	1 BW 2815-2845	
lime	355	shale	1205	shale	2990
shale	370	lime	1215	lime	3068
lime	375	shale	1220	water 2990-3000	
shale	390	lime	1240	Total Depth.	
lime	400	shale	1260		
shale	415	lime	1290		
lime	420	shale	1293	plugged back and drove lead	
shale	430	lime	1310	wool 2770.	
lime	435	shale	1315	Drove lead wool at 2752	
shale	450	lime	1340	drove lead wool and	
lime	470	2 1/2 BW 1320-1330		steel cuttings 2752-2748	
shale	570	shale	1375	cemented hole 2748-2742	
lime	595	shale & shells	1410		
shale	610	lime	1415		
lime	615	shale	1425		
shale	620	lime	1445		
lime	630	sand	1455		
shale	645	HFW 1445			
lime	665	sdv lime	1470		
shale	675	lime	1485		
lime	720	shale	1640		
1 1/2 BW 700-705		sdv lime	1675		
shale	725	lime	1695		
lime	730	sand	1700		
shale	735	7 BW 1695-1700			
lime	770	lime	1800		
shale	795	more water 1730-1735			
		shale	1875		
		lime	1880		

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Locate well correctly on above
Section Plat

WELL PLUGGING RECORD

BUTLER County, Sec. 21 Twp. 28 Rge. 8 (E)E (W)
Location as "NE/CNW&SW" or footage from lines SW SE SE SW
Lease Owner Midwest Supply Company
Lease Name Farrell SWD Well No. 3
Office Address 343 Marmaton Road., El Dorado, Ks 67042
Character of Well (completed as Oil, Gas or Dry Hole) SWD
Date well completed September 18 19 40
Application for plugging filed December 16 19 74
Application for plugging approved December 17 19 74
Plugging commenced December 19 19 74
Plugging completed December 21 19 74
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Ted Dewey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3520 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	2115'	none
				7"	2718	none
				5 1/2"	3020	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Move in, and dig out cellar. Put 5' of rock at 2238' and added 5 sacks of cement to plug the bottom. Put a rock bridge at 110'. Bailed fluid down and dumped in 10 yards of ready-mix cement to plug to surface.

RECEIVED
STATE CORPORATION COMMISSION

JAN 31 1975

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor THE BUCKEYE CORPORATION
Address Box 1020, EL DORADO, KS 67042


STATE OF KANSAS, COUNTY OF BUTLER, ss.
Charles V. Cross (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles V. Cross

Box 1020, El Dorado, Ks 67042
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of DECEMBER 19 74

My commission expires _____



Isa L. Fisher
Notary Public.