

21-28-8E


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - TABLE MESA OIL CO.
Farm - Ferrell No. 20

SEC. 21 T. 28 R. 8E
CNL SW

Total Depth. 2781
Comm. 9-6-49 Comp. 10-18-49
Shot or Treated.
Contractor. Rex & Morris
Issued. 12-3-49

County. Butler
KANSAS



CASING:
13 3/8" 775' P. 7" 2530 P.
10" 1385' P. 5 1/2" 2545' cem. w/60xx.
8 1/2" 1535' P.

Elevation. _____

Production. 30 bbls I. P.

Figures Indicate Bottom of Formations.

cellar	10	shale	1280
lime	20	lime brkn	1310
shale	25	shale	1315
lime	50	lime	1345
red rock	65	shale	1350
lime brkn	90	lime	1395
shale	100	shale	1425
lime	120	lime, shells	1445
red rock	125	sand	1450
lime brkn	135	5 BPH @ 1450	
shale	150	lime	1465
lime	155	shale	1510
shale	165	sand	1525
lime	205	HPW	1510-15
red rock	225	shale	1535
shale	230	Cave @ 1535	
lime	255	shale & shells	1555
shale	260	shale	1685
red rock	265	lime sharp	1700
lime	290	lime	1850
shale	300	shale	1995
lime	340	lime	2005
lime, shells	365	shale	2010
shale	405	lime	2130
shale & shells	420	1/2 BPH @ 2070	
shale	495	bl shale & lime	2140
lime	500	lime	2160
shale	680	bl. shale	2165
lime	685	lime	2195
shale	715	swell of oil @	2170
lime	745	shale	2250
shale & shells	755	lime, shells &	
shale	805	shale	2300
lime	810	shale & shells	2320
shale	845	lime	2330
lime	855	shale	2345
shale	866	lime	2355
lime	865	shells & shale	2395
shale & shells	900	lime sdy	2415
lime	905	lime	2450
shale	980	shale	2455
lime	1020	lime	2490
shale	1030	shale	2555
lime	1055	lime	2565
shale	1065	shale	2650
lime, shells	1100	lime	2670
lime	1110	shale	2735
shale	1115	lime & chat	2745
lime	1125	lime	2750
lime brkn	1140	odor 2745-50	
lime	1170	hard & tgt lime	2760
shale	1185	scant show at	2755
lime	1195	stains only	2755-60
shale	1205	lime	2781
lime	1225	Total Depth	
Cave 1165-1215			
shale	1235	stains 2760-72	
shale, shells	1240	first free oil	2772-79
lime, shells	1255	Tested 30 min.	

some formation wtr.
Increase oil 2779-81