

21-28-8E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- TABLE MESA OIL COMPANY  
Farm- Ferrell No. 25

SEC. 21 T. 28 R. 8E  
SW NW SE  
267'10" SL & 401' WL of NW SE

County Butler  
KANSAS

Total Depth. 2710  
Comm. 6-12-52 Comp. 7-16-52  
Shot or Treated.  
Contractor.  
Issued. 8-30-52



CASING:

8 5/8" 64' cem. w/45 sx  
5 1/2" 2662' cem. w/ 50 sx

Elevation. \_\_\_\_\_

Production. Est. 25 BOPD

Figures Indicate Bottom of Formations.

surface hole	70
lime & shale	350
shale & shells	900
shale & lime	1075
sand	1095
shale & shells	1200
lime & shale	1290
sdv shale	1450
shale & lime	1685
lime	1745
shale & lime	1910
lime	1955
lime & shale	2375
shale & shells	2656
Miss. dolo.	2662, RTD, RB
Miss. dolo.	2659, RTD, DF
lime	2688
lime	2710
Total depth	

Scout Top:  
Mississippi 2656

Remarks:  
Show free oil 2666-75  
Test 1 3/4 gal. oil per hr.  
@ 2681  
Acidize w/3000 gal.  
Acidize w/4000 gal. POP