

18-29-10E

Plotted
L. Norcross

20" 10" 650 FARM Riley Payne NO. 1 COUNTY Elk
 15 1-2 8 1-4 726 COMPANY Ohio Fuel Oil Co.
 12 1-2 16 6 5-8 1218 CONTRACTOR Morrow and Sones.
 TOTAL DEPTH 5 3-16 COMMENCED July 6, 1926 COMPLETED July 22, 1926
 SHOT QUARTS BETWEEN



CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION 1 1/8

REMARKS

10-9-26

Million feet gas.

Formation	Depth	
shale blue	55	Steel line run at 1218. Top of gas
lime white	85	sand at 1246. first gas at 1249.
shale blue	150	Gradually increased to 1256. when
lime white	180	it gaged 1117,240 cu ft 1260 total
shale blue	190	depth last 4' no pay and was drilled
lime white	225	1' through sand
shale blk	230	no Cage used on the anchor. Joint
lime white	235	of 2" was perforated with 30 1/2
shale blue	295	holes perforation 2' off bottom and
lime white	325	11' in length. Packer set in the
shale dark	345	cap rock and a barrel of mud
red rock	355	put on top of it and the casing
shale blue	385	then filled with water after the
lime white	400	well was shut in the tubing showed
shale blue	410	a leak apparently a split joint
lime white	420	about three of four hundred feet
shale blue	435	down the hole. To remedy this leak
4 bailers of water		a 5-3/16 to 2" braden head
sand white	445	was put on the well. A 2" small
shale blue	465	cap used on the bottom of anchor.
lime white	475	
shale blue	495	
lime white	505	
shale blue	515	
red rock	525	
shale blue	560	
lime white	575	
shale blue	645	
lime white	650	
run 10 1/2 casing.		
sand white hard	680	
HFW sd shale white	720	
shale blue	730	
run 8 1/2 casing at 726		
sand white soft	750	
2BW		
sd shale white	765	
sand white	775	
2 bailers of water		
shale blue	842	
lime white	852	
shale blue	895	
lime white	915	
shale blue	920	
lime white	1120	
shale blue	1215	
lime white	1230	
shale blue	1243	
sand grey	1259	
shale white	1260 T.D.	