

OILFIELD RESEARCH LABORATORIES

813 EAST SIXTH
OKMULGEE, OKLAHOMA
PHONE: 1486

- REGISTERED ENGINEERS -

Chanute, Kansas

536 N. HIGHLAND
CHANUTE, KANSAS
PHONE: 728

October 13, 1959

Mr. C. F. Jones
1046 North Waco
Wichita, Kansas

Dear Sir:

WELLS

Attached hereto are the results of saturation tests run on the 3" Rotary core samples taken from the Walls Lease, Well No. 9, located in the NW $\frac{1}{4}$, SW $\frac{1}{4}$, SW $\frac{1}{4}$, Section 9, Township 29S, Range 13E, Elk County, Kansas and submitted to our laboratory on October 12, 1959.

These core samples were wrapped in metal foil and submitted to our laboratory by a representative of the client.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Carl L. McElrea
Carl L. McElrea

CLM:cs

4 c.

Oilfield Research Laboratories

RESULTS OF SATURATION TESTS

TABLE II

Company C. F. Jones Lease WELLS Well No. 9

Sat. No.	Depth, Feet	Effective Porosity Percent	Percent Saturation		Oil Content Bbls./A. Ft.	Feet of Core		Total Oil Content Bbls./Acre
			Oil	Water		Ft.	Cum. Ft.	
1	588.0	22.4	12	67	79			209
2	589.0	24.3	5	79	84			94
3	590.0	25.0	2	79	81			39
4	591.0	23.9	3	85	88			56
5	592.0	24.2	2	87	89			38
6	593.0	23.3	1	89	90			18
7	594.0	23.9	1	91	92			19
8	595.0	16.3	0	83	83			0
9	596.0	21.2	9	69	78			148
10	597.0	21.3	0	87	87			0
11	598.0	11.3	2	88	90			17