

One copy of all wireline logs and drillers time log shall be attached with this form. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

SIDE TWO

Operator Name Everett Morris..... Lease Name Williams..... Well # 6.....
 Sec. 34..... Twp. 29s.. Rge. 15e..... ☒ East ☐ West County Wilson.....

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken ☐ Yes ☐ No
 Samples Sent to Geological Survey ☐ Yes ☐ No
 Cores Taken ☒ Yes ☐ No

Formation Description
☐ Log ☐ Sample

Name Top Bottom

See Attached Log

	Oil	Gas	Water	Gas-Oil Ratio	Gravity
Estimated Production Per 24 Hours	1½ Bbls	10 MCF	5 Bbls	CFPB	23

METHOD OF COMPLETION

Production Interval

Disposition of gas: ☐ Vented ☐ Open Hole ☐ Perforation
☒ Sold ☐ Other (Specify)
☐ Used on Lease ☒ Dually Completed
☐ Commingled

CASING RECORD ☒ New ☐ Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
.....	9 5/8	6 5/8		36	Portland	8	
.....	6 1/2	4 1/2		1280	Portland	142	
.....							

PERFORATION RECORD

Acid, Fracture, Shot, Cement Squeeze Record

Shots Per Foot	Specify Footage of Each Interval Perforated	(Amount and Kind of Material Used)	Depth
2	1199-1210	Water Frac 80 sacks sand	1199-1210
.....			
.....			

TUBING RECORD	Size	Set At	Packer at	Liner Run	☐ Yes ☒ No
.....	2"	1210			

Date of First Production 5-27-83 Producing Method ☐ Flowing ☒ Pumping ☐ Gas Lift ☐ Other (explain).....

WELL RECORD

P 1

API # 20-205-23,376
 Well No. # 6 Farm Williams
 Location 165'E WL-1155'N SL
 Elevation
 Kind (Oil, Gas, Water, Dry Hole) (Oil-Gas)
 Producing formation Top (1199' Bottom 1210-14')
 Shot with qts. from to
 Packer Set at
 Liner from to

Operator # 5545
 Producer Iverett, Morris.D B A- N&O oil co.
 Sec. 34 Twp. 29 S Rg. 15 E
 State Kansas County Wilson
 Contractor Way Drilling co.

LOG

Thick- ness	Strata	Depth	Thick- ness	Strata	Depth
4	Soil Rock shale	4	13	Sand (nice)	702
9	Lime gy hard	12	31	Shale gy sdy	773
2	Lime wt Yellow	34	1	Coal	774
7	Lime gy	41	5	Shale gy sdy	779
16	Shale gy	57	8	Sand (calcified)	787
86	Lime w/shl	143	50	Shale gy sdy	837
13	Shale gy lm	156	4	Lime br	841
118	Shale gy	274	1	Coal	842
3	Lime br	277	8	Shale gy sdy	850
6	Shale gy TCT	282	17	Lime (40')	867
53	Sand (V Salty)	335	5	Slate shl dk	872
10	Shale lt dk TCT	365	22	Shale dk gy	900
7	Slate shl dr	372	29	Lime (20')	929
8	Shale gy sdy	380	7	Slate dk	936
10	Sand gy	390	12	Lime (5')	948
2	Lime br	392	5	Slate shl coal	953
6	Shale gy sdy	398	6	Lime	959
5	Lime br	403	45	Shale gy sdy dk	1004
7	Slate shl dk	410	1	Coal	1005
17	Lime br wt gy	427	18	Shale gy sdy	1023
7	Shale gy	434	3	Lime (2')	1026
73	Lime gy wt br	507	18	Sand shl lm	1045
28	Sand gy (Salty)	535	23	Shale dk w/lm	1068
7	Shale gy	544	1	Coal	1069
29	Lime br	573	15	Shale G S lm st	1084
22	Shale gy LCO	615	1	Coal	1085
11	Lime br dk hrd	626	14	Shale dk gy sdy	1099
6	Slate bl	632	1	Coal	1100
39	Shale dk G O	671	8	Sand dk V F O	1108
6	Lime	677	25	Shale dk sdy	1133
16	Sand w/shl GO	693	1	Coal	1134
2	Lime	695	25	Shale gy sdy	1159
4	Sand	699	40	Sand gy FOO	1199
8	Shale gy sdy GO	707	2	Sand gy oil slt	1201
15	Lime	722	9	Sand O Bld core	1210
7	Shale sand lm	729	4	Sand VLB/gas	1214

Open Hole

Casing at 36'
 Casing 6 5/8" at 36'
 Casing 4 1/2" at 1280'
 Cement The 4 1/2" to the surface

Tubing

Rods

Additional Information

2 Sand lite bld--w/gas 1216
 10 Sand w/odor (coal) shls (B&G) 1226
 13 Sand Lite (Free oil when drilled.
 -- Smells Piney 1239
 18 Shale dark to gy 1252
 2 Coal 1259
 5 Shale gray 1264
 1 Coal 1265
 15 Shale gy to dk (T.D.) 1280

Core and time on back of page

Date Completed 4/25/83--4/27/83

O. K.

Superintendent

34-29-15E

W O oil co. etal
Williams lease
well # 6
Core # 1

	Min.	Sand	oil	bleed	with gas	from--	1201
2	"	"	"	"	"		1202
2	"	"	"	"	"		1203
2	"	"	"	"	"		1204
1	"	"	"	"	"		1205
1	"	"	"	"	"		1206
2	"	"	"	"	"		1207
1 1/2	"	"	"	"	"		1208
2	"	"	"	"	"		1209
1 1/2	"	"	"	"	"		1210
1 1/2	"	Sand	oil	V lite bleed	"		1211
2	"	"	"	"	"		1212
2	"	"	"	"	"		1213
2	"	"	"	"	"		1214
2 1/2	"	Sand	oil	lite bleed	"		1215
2	"	"	"	"	"		1216
2	"	Sand	W/odor	(Carbon streak middle this foot)	Some gas		1217
2	"	"	"	"	"		1218
2	"	"	"	"	"		1219
2	"	"	"	Carbon streak middle this foot	"		1220
2	"	"	"	Coal middle this foot	"		1221
2 1/2	"	"	"	Carbon streak middle this foot	"		1222
2 1/2	"	"	"	"	"		1223
2 1/2	"	"	"	"	"		1224
3	"	"	"	Carbon streak middle this foot	"		1225
3	"	"	"	"	"		1226

(Bottom of core) 1226'