

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form ACO-1  
September 1999  
Form Must Be Typed

WELL COMPLETION FORM  
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 32606  
Name: Devon Energy Production Company, LP  
Address: 20 North Broadway, Suite 1500 Attn: Robert Cole  
City/State/Zip: Oklahoma City, OK 73102-8260  
Purchaser: Tall Grass, LLC  
Operator Contact Person: Robert Cole  
Phone: (405) 235-3611  
Contractor: Name: Mokat Drlg.  
License: #5831  
Wellsite Geologist: David Flemming  
Designate Type of Completion:  
 New Well  Re-Entry  Workover  
 Oil  SWD  SLOW  Temp. Abd.  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expl., Cathodic, etc)  
If Workover/Re-entry: Old Well Info as follows:  
Operator: Devon SFS Operating, Inc.  
Well Name: Glen Berg # 32-1  
Original Comp. Date: 11-20-2001 Original Total Depth: 1095  
 Deepening  Re-perf.  Conv. to Enhr./SWD  
 Plug Back  Plug Back Total Depth  
 Commingled  Docket No. \_\_\_\_\_  
 Dual Completion  Docket No. \_\_\_\_\_  
 Other (SWD or Enhr.?)  Docket No. \_\_\_\_\_  
8-9-02 9/21/01-TD 8-13-02  
Spud Date or Date Reached TD Completion Date or  
Recompletion Date Recompletion Date

API No. 15 - 205-25420 - 0001  
County: Wilson  
\_\_\_\_\_ SW Sec. 32 Twp. 29 S. R. 17  East  West  
1200 feet from S N (circle one) Line of Section  
1600 feet from E W (circle one) Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE SE NW SW  
Lease Name: Glen Berg Well #: 32-1  
Field Name: \_\_\_\_\_  
Producing Formation: Cherokee Coal  
Elevation: Ground: 875 ft. Kelly Bushing: \_\_\_\_\_  
Total Depth: 1,095 ft. Plug Back Total Depth: 1,082 ft.  
Amount of Surface Pipe Set and Cemented at 33 Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set \_\_\_\_\_ Feet  
If Alternate II completion, cement circulated from Surface  
feet depth to 1,089 ft. w/ 155 sx cmt.

**Drilling Fluid Management Plan**  
(Data must be collected from the Reserve Pit)  
Chloride content N/A ppm Fluid volume N/A bbls  
Dewatering method used \_\_\_\_\_  
Location of fluid disposal if hauled offsite: \_\_\_\_\_  
Operator Name: \_\_\_\_\_  
Lease Name: \_\_\_\_\_ License No.: \_\_\_\_\_  
Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  East  West  
County: \_\_\_\_\_ Docket No.: \_\_\_\_\_

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Robert Cole  
Title:  Sr. Eng. Tech. Date: 4/7/03  
Subscribed and sworn to before me this 15th day of April, 2003  
Notary Public: Shamir Plaster

**KCC Office Use ONLY**  
 Letter of Confidentiality Attached  
If Denied, Yes  Date: \_\_\_\_\_  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution

Operator Name: Devon Energy Production Company, LP Lease Name: Glen Berg Well #: 32-1

Sec. 32 Twp. 29 S. R. 17  East  West County: Wilson

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

<p>Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i></p> <p>Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No</p> <p>Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No</p> <p>Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i></p> <p>List All E. Logs Run:  GR, N, D, DIL, CBL</p>	<p><input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input checked="" type="checkbox"/> Sample</p> <p>Name Top Datum</p> <p>See Attachments</p>
---	---

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	11"	8 5/8"	32 #/ft	33'	Portland	8	none
Production	7 7/8"	5 1/2"	15.5 #/ft	1,089'	CI "A"	155	ThickSet

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
___ Perforate				
___ Protect Casing				
___ Plug Back TD				
___ Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
4 spf	1,017'-1,020'-Riverton	500glsFeHCl,Frac855Bbls20,000 lbs20/40	
4 spf	993'-996'Neutral,971'-972',965'-968Rowe	500glFeHCl,Frac456Bbls4,000lbs20/40Sd.	
4 spf	622'-626'Mulky,609'-613'Summit	500glFeHCl,Frac417Bbls5,500lbs20/40Sd.	

TUBING RECORD		Size	Set At	Packer At	Liner Run	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
		2 7/8"	1,061'-EOT	N/A		
Date of First, Resumed Production, SWD or Enhr.		Producing Method				
11/27/01		<input checked="" type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)				
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity	
	N/A	130 Mcfd	277 bwpd	N/A	N/A	

Disposition of Gas      METHOD OF COMPLETION      Production Interval

Vented  Sold  Used on Lease  Open Hole  Perf.  Dually Comp.  Commingled  
*(If vented, Sumit ACO-18.)*  Other (Specify)