

29-29-17E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- WHITE & ELLIS DRILLING COMPANY  
Farm- Osborn No. 1

SEC. 29 T. 29 R. 17E  
NE NW NE

Total Depth. 703'  
Comm. 1-15-54 Comp. 2-5-54  
Shot or Treated.  
Contractor.  
Dated. 8-20-60

County Wilson  
KANSAS



CASING:  
10" @ 23'  
8" @ 511'  
7" @ 605'  
5" @ 760'

Elevation. \_\_\_\_\_

Production. Dry

Figures Indicate Bottom of Formations.

soil	2
clay	15
shale	20
gravel	22
shale	24
lime	33
shale	45
lime	130
shale	143
shale, sandy	156
lime	185
shale, gas	192
lime	255
shale	293
lime shells	311
shale shells	349
lime	357
shale	426
sand - gas	436
shale, sandy	447
sand - water	465
sand	466
lime	499
shale	501
lime	503
shale	511
shale, sandy	525
sand	527 1/2
shale, sandy	547
lime	569
shale	570
shale - water	576
lime	585
shale	595
lime	600
shale	620
shale, sandy - show of oil	677
sand - broken -- show of oil	703
Total Depth	