

17-29-8E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- BEAUMONT PETRO. CO.  
Farm- Bessie Weberman No. 2

SEC. 17 T. 29 R. 8E  
NW SE NW

Total Depth. 2825'  
Comm. 10-24-55 Comp. 11-17-56  
Shot or Treated.  
Contractor. Beaumont Petro. Co.  
Issued. 9-26-59

County Butler  
KANSAS



Elevation. 1525' RB

Production. 15 bbls.

CASING:

10 3/4" 33' w/40 sx cem.  
7" 2825' w/50 sx cem.

Figures Indicate Bottom of Formations.

RB 5' above G.L.	
cellar	5
shale, lime	40
lime, shale brks	650
shale, shells	800
lime, shale	890
lime, shale brks	1085
lime, shale	1540
shale, lime	1860
shale	1920
lime	2167
shale	2202
sdv shale	2253
lime	2410
shale	2610
shale, lime	2700
lime	2825 RTD
Cable Tool	
lime	2810 Eff. T.D.

TOPS:

Kansas City ls	1920
B/Kansa City ls	2154
Marmaton ls	2253
Cherokee sh	2410
Mississippi ls	2700