

DRILLING SUPERVISION REPORT

David Fleming

ORIGINAL

P.O. BOX 253
CANEY, KANSAS 67333

HOME # (620) 879-2291 CELL # (620) 252-9985

COMPANY		LEASE		FIELD	
Devon		Woolery SDW 21-1			
SEC	TWP	RGE	COUNTY	STATE	DATE
21	29	18	Neosho	Ks	11-5-02
LOCATION				ELEV.	
650' FSL - 1350' FEL				1058'	

REMARKS
Mulberry, Lexington, Summit, Mulkey, Bevier, Croweberg, Fleming, Tebo, 1 st & 2 nd Row, Riverton, miss. - Lt. oil show

FROM	TO	FORMATION DESCRIPTION	FROM	TO	FORMATION DESCRIPTION
75	141	Shak (went to water) good stream			making lots of water
434	443	Lenapah Lime	1372	1391	Kinderhook shak
461	466	Altamont Lime	1391	1406	Comptain Lime
565	606	Pawnee Lime	1406	1414	Chattanooga Shale
569	570	Mulberry Coal - few gas bubb.	1418	1418	Arbuckle
640	641	Lexington Coal - good gas bubb	1418		Gas ck same T.P.
643	686	Oswego Lime			
665	676	Summit - good gas bubb			
680	684	Mulkey - good gas bubb			
684		Test 4" on 1/4" = 19,000			
758	760	Bevier Coal - few gas bubb			
783	784	Croweberg - very few gas bubb.			
821	822	Fleming Coal - few gas bubb			
837	838	mineral Coal - Lt. Pyrite. no gas			
883	884	Tebo Coal - very few bubb.			
924		Test 4" on 1/4" = 19,000			
1045	1047	1 st Row few gas bubb			
1052	1055	2 nd Row few gas bubb			
1066		Hand ck same blow			
1065	1066	Natural Coal - very few gas bubb			
1101	1104	Riverton - few gas bubb. (water)			
1121	1372	miss. - Lt. oil show			
		from 1125-1135			
1124		Hand ck - same blow - well			