

Company

Sec. 6 T. 29 R. 22E
Loc. C of NL of NE $\frac{1}{4}$ SW $\frac{1}{4}$

Farm Youse

No. 2

Total Depth 415

County Crawford


Comm.

Comp. Aug 28-39

Shot or Treated

Contractor

Issued



Casing

20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Elevation

Production

Figures Indicate Bottom of Formation

9 surface	9
3 sandstone	12
15 gray shale	27
63 lt gray sandy shale	90
11 dark gray shale	101
32 limestone	133
2 dark shale	135
15 dark gray shale	150
20 light shale	170
15 dark shale	185
11 dark shale	196
21 limestone	217 (Ft. Scott)
7 dark shale	224 gas
6 Oswego limestone	230
5 dark shale	235
25 gray shale	260
8 gray shale	268
12 dark shale	280
5 gray shale	285
15 dark shale	300
20 dark shale	320
4 dark shale	324
10 dark shale	334
6 limestone	340 gas & dark shale
5 gray shale	345 strong gas
10 gray shale & ss	355
3 1/2 gray shale	358 1/2 sandstone & s.o.
5 gray sandstone	363 oil show
22 sandstone	387 oil show
10 sandy shale	397
5 brown sandstone	402 oil show and Gas
4 dark sandstone	406 oil and Gas
4 dark sandy shale	410
5 dark shale	415

Shot 26' of sandstone

E P