

V W & B DRILLING CO.  
Box 7 N. Hwy. 169  
CHERRYVALE, KS 67335

State Geology  
WICHITA BRANCH

Frank Oplotnik #1

Sec. 18 T29S R22E  
Loc. W 1/2 SE 1/4 570' from South line  
660' from East line.  
County: Crawford

Gas Well

Commenced Drilling 8-11-80  
Completed Drilling 8-12-80

Figures indicate the bottom  
of the formation

1	Top Soil	1	14	Dk. Shale	153
6	Yellow Clay	7	6	Lt. Shale	159
11	Sandstone	18	4	Sandy Shale	163
22	Gray Shale	40	14	Lt. Shale	177
15	Sandy Shale	55	27	Gray Shale	204
50	Gray Shale	105	20	Lime	224
21	Lime	126	7	Blk. Shale (Gas)	231
2	Blk. Shale	128	7	Lime	238
8	Lime	136	5	Blk. Shale (Gas)	243
3	Blk. Shale	139	4	Lt. Shale	247

Hole Size 4-3/4"

30 feet of 5-1/2" casing. 210' of 1 inch black pipe with packer and lead seat for 3/8" seating nipple. 12' of 3/8" brass pipe. 198 feet of drisco pipe set on inside of 1 inch pipe. Packer set at 210'.

STATE CORPORATION COMMISSION  
RECEIVED  
SEP - 8 1980  
CONSERVATION DIVISION  
Wichita, Kansas