


Slawson, Hagen et al.
Farm M.G. Slawson No. 1

Loc. SE 1 NE 1 NW 1

Total Depth 407'
Comm.
Shot or Treated
Contractor K.W. Hagen
Issued

County Crawford



Casing
20 in. 10 in.
15 1/2 8 1/4
12 1/2 6 5/8
13 3/8 5 3/16

Elevation

Production Dry hole

Figures Indicate Bottom of Formation

5 surface
15 clay
Bever 32 dark shale and coal
34 limestone
36 dark shale
37 limestone
50 dark shale
65 light shale
Crown 75 dark shale and coal
85 gray shale
90 dark shale
91 limestone
Min 100 shale and coal
115 gray shale
120 dark shale
145 dark shale show of gas
170 gray shale
175 dark shale
WP 178 coal
185 shale and coal
215 dark shale
265 light shale
290 sandy shale and shells
300 dark and brown shale
340 dark and brown shale
350 sandstone, show of gas
355 shale
Moline 376 sandstone, shale, show of gas
379 limestone and chat.
576 407 flint and limestone