

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Dean Bolick, Eng.
at Frontenac, Mo.
this is the RRWD.

Company (CITY OF CROWEBURG, OWNER)
Farm—Croweburg No. 1

Rural Water Dist #3
4-29-25E
SEC. 4 T. 29 R. 25E
SE SE NE

Total Depth. 986'
Comm. 11-6-61 Comp. 12-21-61
Shot or Treated.
Contractor. C. E. Abercrombie Drig. Co.
Issued. 1-27-62

County Crawford
KANSAS



CASING:
7 1/4" 385' cem w/180 sx.

Elevation. ??

Production. Water

Figures Indicate Bottom of Formations.

11	soil & clay	480	gray & brown lime; gray flint
14	gray shale, lime streaks	490	dark gray lime; brn lime; gry flint
16	coal	495	drak gry lime; white flint
17	underclay	515	white flint, dark gray lime
20	dark gry shale, lime strks.	550	white & gray flint; dark gray lime
23	gray shale	560	white & gry flint; gray lime, sandy
25	coal	565	white & gray flint
26	underclay	590	white & gray flint; gray lime
33	gray shale	600	dark gray & blue flint; brown lime
50	dark gray shale	610	gray flint; gray lime
58	light gray shale	615	gray lime, gray flint
59	coal & underclay	620	gray lime; gray & brown flint
75	gray shale	625	gray & brown flint
81	dark gry shale	630	gray & brn flint; gry & brn lime
85	black shale	640	brown lime & gray flint
105	gray sandy shale; limestone strks.	645	gray shale
107	brown limestone	660	gray-blue shale
124	gray shale	685	gray shale
125	brown limestone	700	gray lime
127	coal & underclay	720	gray & white flint; green shale; gry limestone
146	light gray shale; limestone strks,		
149	coal	725	gray lime
151	underclay	735	gry lime; blue & white flint
160	light gray shale	750	gray lime; gray flint
178	dark gray shale; trace coal & lime	755	gray lime; gray & white flint
180	light gray shale	760	brown lime; gray & white flint
184	light gray sandstone	765	brown lime; blue & gray flint
190	drk gry shale, trace limestone	785	gray lime; blue & gray flint
207	light gray sandstone, micacious	795	blue, gray & white flint
212	black shale	800	gray & brown sandy lime
213	coal & underclay	820	gray & blue flint; gray lime
225	dark gray shale	840	gray & brown lime; blue & gray flint
245	gray shale; lime streaks	865	white & gray flint; gray lime
250	light gray micacious sandstone	880	dark gray & brown limestone; gry flint
251	dark gray limestone	890	sandstone
253	coal	895	sandstone; dark gray & brn limestone
255	underclay & shale	910	dark gry & brn sandy limestone, gry flint
264	gray shale, sandy		
266	black limestone	915	sandstone; white flint
267	coal	925	sandstone
269	underclay	940	gray sandy lime
280	light gray shale, micaceous	945	gray sandy lime; gray flint
283	dark gray shale	960	gray sandstone
290	brown limestone	965	dark gray lime; sandstone
294	coal & underclay	986	gray sand
297	light gray sandy shale		Total Depth
299	gray sandstone		
316	dark gray to black shale		
319	gray sandstone		
322	gray shale		
341	gray sandstone		
348	dark gray shale		
355	gray lime; black & gray flint		
360	gray lime; blue flint		
380	gray lime; blue & gray flint		
390	gray flint; gray lime		
405	gray & blue flint; gray lime		
425	brown lime; gray flint		
445	gray lime; gray flint		
450	gray & brown lime; gray flint		
470	gray & brown lime		