

CONFIDENTIAL

SIDE ONE



AFFIDAVIT OF COMPLETION

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Kennedy & Mitchell, Inc.

API NO. 15-015-21,884

ADDRESS P.O. Box 270
Denver, CO

COUNTY Butler

FIELD Wildcat

**CONTACT PERSON Robert A. Baker
PHONE 303-988-4620

PROD. FORMATION

LEASE Blood

PURCHASER

WELL NO. 39-521-3

ADDRESS

WELL LOCATION SW SW SE

330 Ft. from South Line and

2310 Ft. from East Line of

the 23 SEC. 29S TWP. 4E RGE.

DRILLING Ramco Drilling Corporation
CONTRACTOR
ADDRESS P.O. Box 204
Wichita, KS 67201

WELL PLAT

Grid for well plat with 4 columns and 4 rows.

KCC
KGS
(Office Use)

RELEASED
Date: 1 NOV 1982
FROM CONFIDENTIAL

PLUGGING Ramco Drilling Corporation
CONTRACTOR
ADDRESS P.O. Box 204
Wichita, KS 67201

TOTAL DEPTH 3000' PBD

SPUD DATE 10/25/81 DATE COMPLETED 11/4/81

ELEV: GR 1275' DE 1278' KB 1280'

DRILLED WITH (CABLE) TOOLS

Amount of surface pipe and cement 210'

DV Tool Used?

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1982
CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

STATE OF Colorado, COUNTY OF Jefferson ss, I, Robert

A. Baker OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Engineer (FOR)(OF) Kennedy & Mitchell, Inc.

OPERATOR OF THE Blood LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 39-521-3 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 4th DAY OF November, 19 81, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

31-2-42
SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Rock & Clay	0'	40'	RTD	23-29-4E
Rock	40'	90'		
Surface, Clay & Sand	90'	230'		
Clay & Sand	230'	354'		
Clay, Sand & Shale	354'	790'		
Sand & Shale	790'	1470'		
Shale	1470'	2200'		
Lime & Shale	2200'	2340'		
Shale & Lime	2340'	2780'		
Lime & Shale	2780'	3000'		

Report of all strings set — surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	24#	210'	Class H	150	3% CC

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		
Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

W E L L L O G

State Geological Survey
WICHITA BRANCH

23-29-46

WELL NAME: Blood #3-39-521

OPERATOR: Kennedy & Mitchell

SPUD DATE: 10-25-81

CONTRACTOR: Ramco Drilling Company

COMPLETION DATE: 11-4-81

CASING: 8 5/8 24# new, set @ 210'
w/150 sx cmn, 3% cc . plg down
@ 10:30 a.m., 10-27-81.

LOCATION: SW SW SE
Sec. 23-29S-4E
Bulter county, Ks.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Rock and Clay	0	40
Rock	40	90
Surface, Clay and Sand	90	230
Clay and Sand	230	354
Clay, Sand and Shale	354	790
Sand and Shale	790	1470
Shale	1470	2200
Lime and Shale	2200	2340
Shale and Lime	2340	2780
Lime and Shale	2780	3000
RTD	3000	

23-29-4E

KENNEDY & MITCHELL, INC.

ELEV: GL 1275'

Blood #39-521-3
SW SW SE Sec. 23-29S-4E
Butler Co., KS
3000' Miss.
Cont. Ramco

7400 WEST JEFFERSON AVENUE
DENVER, COLORADO 80235
TELEPHONE 303-988-4620

DAILY DRILLING REPORT

State Geological Survey
WICHITA BRANCH

Page 1

10/26/81

TD 43'. Drlg rathole. Spudded @ 10:30am 10/25/81. Rig repair.

10/27/81

TD 220'. Prep to run surface csg.

RELEASED
Date: 1 OCT 1982
FROM CONFIDENTIAL

10/28/81

Drlg @ 350' w/fresh wtr. Ran 5 jts 8-5/8" 24#, K-55 csg. Set @ 210'. Cmt w/ 150 sks
Class H, 3% CC. Cmt circ. Plug dwn @ 11:30am 10/27/81.

10/29/81

Drlg @ 1435' w/fresh water.

10/30/81

Drlg @ 2200'. Vis 36. WT 9.2.

10/31/81

Drlg @ 2572'. Vis. 47. WT 9.4.

11/1/81

Drlg @ 2850'. Vis. 36. WT 9.4. WL 12. Top of L. Bartlesville Sand 2820' (-1540')
Base Sand 2840' (-1560')

11/2/81

TD 2925'. DST #1 from 2882'-2925'. Misrun, hole in DP. DST #2 from 2882'-2925',
15-30-15-30. IF 45-45#. ISIP 56#. FF 45-45#. FSIP 45#. Rec 30' DM, no show.

11/3/81

TD 3000'. Petro Log ran N/D & DIL logs. Top of Miss-Lime 2933' (-1653')

11/4/81

TD 3000'. DST #3 from 2834'-2895', 15-30-60-120. IF 30-30#. FF 55-55#. ISIP 400#.
FSIP 85#. Rec 60' DM, no show.

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1982

CONSERVATION DIVISION
Wichita, Kansas