

F.W. MORGAN
GEOLOGIST

305 S. WASHINGTON
ELDORADO, KANSAS 67042

April 17, 1985

(316) 263-0134
ELDORADO (316) 321-1483

Razook Oil Company
R. R. # 4, Box 102
Augusta, Kansas, 67010

Re: No. 3 Razook "B"
Sec. 16-29S-4E
Butler County, Ks.

Gentlemen:

Enclosed is my geological report on the above captioned well. The Well ran 9 feet lower than the plugged well to the northeast and 13 feet lower than the one to the southeast on the Lansing formation. On the Arbuckle formation it was 8 feet lower than the one northeast and 35 feet lower than the one southeast.

Shows of oil were logged in the Lansing from 1836 feet to 1856 feet, consistent with the zones produced in the abandoned wells on the lease and production in the area.

Shows of oil were also logged in the Arbuckle, but it was condemned by the drill stem test described on my log.

Casing was run to a depth of 1922 feet to perforate and test the Lansing for production. It is my recommendation that perforations be limited to the upper part of the zone subject to log correlation.

Sincerely,


F. W. Morgan





LAUGHLIN-SIMMONS & CO. OF KANSAS, INC.

OIL FIELD SURVEYING
1337 NORTH MERIDIAN, SUITE 2
WICHITA, KANSAS 67203

(316) 943-5351

KW1038510

INVOICE NO.

RAZOOK OIL COMPANY

OPERATOR

3

NO.

Razook

FARM

Butler

COUNTY

16

S

29s

T

4e

R

CN/2 NW/4

LOCATION

ELEVATION:

1196 gr



RAZOOK OIL COMPANY

R. R. 4 Box 102

Augusta, Kansas 67010

AUTHORIZED BY: Frank Morgan

SCALE: 1" = 1000'

660

1320

STAKE

OLD POOL

TANK BATTERY

16

5' Rebar & Plastake in level
milo stubble

Ingress E or N
Flag N, NE, SE

RAILROAD



"DOUGLASS"