

F.W. MORGAN
GEOLOGIST

305 S. WASHINGTON
ELDORADO, KANSAS 67042

Dec. 11, 1985

(316) 263-0134
ELDORADO (316) 321-1463

Crest Petroleum, Inc.
P. O. Box 445
Andover, Kansas, 67002

Re: No. 1 McCune
Sec. 33-29S-5E
Butler County, Ks.

Gentlemen:

Following is my report on the McCune well and enclosed is my Geological Log which has all pertinent geological information on it. The well ran slightly high to the Bartlesville producer to the east. Iatan at 1758' was 1 foot high; Kansas City at 2137' was 9 feet higher;; and Bartlesville at 2766' was 13' feet higher, all based on log tops. Shows of oil and/or gas were as follows:

Kansas City - 2152' - 2156'- From samples and from log calculations this zone appears to have some merit. It should be tested before abandoning the well.

Bartlesville - 2766' - 2798' - There were good shows of oil and gas throughout the entire sand body. By samples and log calculations the section from about 2790' to base appears to be water productive. My recommendation is to perforate from about 2767' to 2776'.

Casing was run to complete this well for production.

Sincerely,


F. W. Morgan





LAUGHLIN-SIMMONS & CO. OF KANSAS, INC.

OIL FIELD SURVEYING
1337 NORTH MERIDIAN, SUITE 2
WICHITA, KANSAS 67203

(316) 943-5351

KC1117851

INVOICE NO.

CREST PETROLEUM INC. _____
OPERATOR

1
NO.

McCune _____
FARM

Butler _____
COUNTY

33 29s 5e
S T R

200' N of SE SE SE _____
LOCATION

ELEVATION: 1247 gr



CREST PETROLEUM INC.
Box 445
210 Ira Court
Andover, Kansas 67002

AUTHORIZED BY: Gene McAllister _____

2 miles to
"SMILEYBERG"

SCALE: 1" = 1000'

