

508 East Murdock
Wichita, Kansas

WELJ ECORD

13-29-8E
1/2 50 NW

Well. No. 1-A Farm Youngmeyer Producer Hutchison Oil Co.
Location C. E. 1/2 SW 1/4 Sec. 13 Twp. 29S Rge. 8E
Elevation 1404' 6R State Kansas County Elk
Kind (Oil, Gas, Water, Dry, Hole) Oil Contractor B & N Drilling Co.
Producing Formation _____ Top _____ Bottom _____
Shot With _____ Qts. _____ from _____ to _____
Packer Set At _____ Kind _____ Size _____
Liner _____ from _____ to _____ Perforated from _____ to _____



Thick- ness	Strata	Depth	Thick- ness	Strata	Depth
4	Soil	4	133	Limestone & Shale	967
12	Clay	16	29	Shale	996
24	Limestone	40	12	Limestone	1008
34	Shale	74	18	Shale	1026
29	Lime	103	4	Limestone	1031
6	Shale	109	7	Shale	1038
4	Lime	113	3	Limestone	1041
4	Shale	117	67	Limestone/Shale	1108
5	Lime	122	60	Shale	1168
47	Shale	169	33	Limestone	1201
3	Lime	172	89	Shale	1290
254	Shale	426	70	Sandy Shale	1360
22	Lime	448	110	Shale w/Lime strks	1470
33	Shale	481	4	Lime	1474
25	Lime	506	54	Shale/Limestone	1528
4	Shale	510	13	Lime	1541
83	Shale/Limestone	593	114	Shale/Limestone	1655
18	Lime	611	28	Lime	1683
20	Shale	631	20	Shale/Limestone	1703
9	Shale/Limestone	640	16	Lime	1719
13	Lime	653	81	Shale/Limestone	1800
2	Shale	655	8	Lime	1808
10	Lime	665	130	Shale/Limestone	1938
94	Shale	759	38	Limestone	1976
14	Shale/Limestone	773	11	Shale	1987
8	Lime	781	7	Limestone	1994
9	Shale	790	60	Shale	2054
29	Lime	819	5	Limestone	2059
9	Shale	828	91	Shale	2150
6	Limestone	834	21	Limestone	2171

Total Depth 2969'

Open Hole _____

Casing _____ at _____

Casing _____ at _____

Casing _____ at _____

Cement _____

Tubing _____

Rods _____

Additional Information Drill Stem Test:

2018-2035 - Open one hour, recovered

928 feet gas and 288 feet of

slightly mud cut gassy oil/

251 feet of oil and gas cut

wattery mud / 198 feet of salt

water.

Sample 2017

BKC 2058

2252

2298

2330

2616

2920

Arbuckle 2967

DDTD 2989 1/2

Date Completed _____

75	Shale	2246
49	Limestone&Shale	2295
17	Lime	2312
10	Black Shale	2322
8	Lime	2330
294	Shale/Limestone	2624
313	Miss. Lime	2937
21	Shale	2958
11	Arbuckle Lime	2969

Open Hole _____

Casing _____

Casing _____

Casing _____

Cement _____

Tubing _____

Rods _____

13-29-8E