


20" 10" 1265 FARM J. H. Porter NO. 1 COUNTY
 8 1-4 1992 COMPANY Allison & Fitzwilliam
 15 1-2 19 6 5-8 CONTRACTOR J. E. Brinogar, Fredonia, Kansas.
 12 1-2 1026 5 3-16 COMMENCED Feb. 11, 1927. COMPLETED March 28, 27.
 TOTAL DEPTH 2032½' SHOT 95 QUARTS BETWEEN
 CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Allison & Fitzwilliam,
 612 Brown Bldg., Wichita, Kansas. ELEVATION
 FIGURES INDICATE BOTTOM OF FORMATIONS. INITIAL PRODUCTION
 REMARKS 4/16/27.



Formation	Depth	Formation	Depth
lime	15	shale	1075
shale blue	25	lime	1087
limo	35	shale	1092
shale	45	limo	1105
lime	48	shale	1135
sandy shale	78	red rock	1160
lime	88	shale blue	1165
shale	148	shale blue	1170
lime	158	lime	1175
shale	203	shale blue	1208
lime	218	red rock (Bad cave 1223')	1223
shale	275	shale blue	1265
lime	285	shale blue (Hole dry	1280
shale	300	lime	1285
lime	315	shale sandy	1345
shale	325	lime	1355
lime	350	shale blue	1455
shale	360	lime	1490
lime	365	shale blue	1550
shale	375	lime	1645
lime	405	lime	1670
shale	408	shale	1685
lime	418	lime	1805
shale	428	sand Dry	1825
lime	440	lime	1947
shale	455	slate	1958
lime white	480	lime	1975
shale light	525	slate (Show oil)	1986
lime hard	530	lime	1997
shale	575	sandy lime (Pay Oil)	2029
lime	595	slate	2032½
shale	630	2032½ Total Depth	
lime white	650	NOTE: Hole reduced at 1992'. First oil and gas at 1997'. More oil to 2028. Hole filled up 1000' before shote. Shot with 95 quarts. Hole cleaned out filled up 1500'.	
shale black	655		
lime hard	670		
shale	695		
lime	710		
shale	715		
lime	780		
shale	785		
lime	795		
shale	805		
lime	820		
shale	830		
red rock	840		
lime (Bad cave--855')	855		
shale	895		
lime	910		
shale	940		
lime	955		
shale (HFW 1010')	1010		