

3-2-14E ✓

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- BRUNSON SPINES
Farm- Bahr No. 1

SEC. 3 T. 2 R. 14E
C W $\frac{1}{2}$ SW SW

Total Depth. 3548
Comm. 3-20-65 Comp. 3-30-65
Shot or Treated.
Contractor. Woodman Iannitti Drlg.
Issued. 6-12-65

County Nemaha

KANSAS



Elevation. 1306' KB

CASING:

8 5/8" 212' cem w/ 150 sx
5 1/2" 3544 Figures Indicate Bottom of Formations.

Production. 25 BOPD NW

Dolomite buff	2478
Dolomite tan to brown medium crystalline	2844
Dolomite white to tan no show basal portion carrying chert & Quartz veining	2966
Dolomite tan	2992
Dolomite white to tan	3090
Dolomite white to light blue-gray	3440
Dolomite-pink buff	3456
Dolomite tan to buff	3488
Dolomite tan good show free oil, good staining	3548
Total Depth	

TOPS: LOG

Mississippian limestone	2478
Kinderhook shale	2583
Hunton	2818
Maquoketa	3488
Viola	3543

DST # 1 3544-48 Op 10 min for pre-flow, shut in 20 min. Op 1 hr. Weak blow at beginning, increasing to strong blow at end of test shut in 20 min. Rec. 210' clean oil and 30' of heavily oil cut mud, no gas, no water. IFP 12#, IBHP 644#, FFP 94#, FBHP 613#, BH tem 104°F.