

Company - FRED D. CULPEPPER
Farm - Frederick Lamparter No. 1.

SEC. 3
CW $\frac{1}{2}$ SW SE

T. 2

R. 14 E

Total Depth. 2900'

Comm. 11-14-44

Comp. 12-1-44

Shot or Treated.

Contractor.

Issued. 12-30-44


CASING:

8 5/8" 63° Cem.

County.

Nemaha

KANSAS



Elevation. 1311

Production.

Dry

Figures indicate Bottom of Formations.

clay	0-38	shale lime & granite	
sand	46	wash & sand streaks	2163
shale & clay	60	shale & granite wash	
shale & shells	165	& lime streaks	2236
lime	175	shale & granite wash	
shale & shells	265	& lime	2262
lime	275	shale & lime shells	2306
shale	400	shale & lime streaks	2346
lime	430	shale & shells &	
clay & sand	590	granite wash	2380
shale, shells & lime	745	shale	2447
lime	770	lime chert	2515
shale & sand	845	lime	2578
lime	890	shale	2662
lime & shale	960	hematite	2666
sand	1025	shale	2830
shale & lime	1047	lime Hunton	2832
lime	1070	lime hrd	2840
lime & shale	1085	lime	2857
lime	1155	lime & shale	2891
lime & shale	1280	lime	2900
lime	1350	Total Depth	
lime & shale	1380		
lime	1417	Top Hunton lime	2830
lime & shale	1432		
lime	1441	Drilled in to	2840
lime & shale	1536	cored	2840 -57
lime	1568	sli.oil stains	2840-50
lime & shale	1596		
lime hrd	1606		
lime & shale sand	1636		
shale & lime	1690		
granite wash &			
lime & shale	1710		
granite wash &			
shale	1722		
granite wash &			
shale & lime	1760		
shale & granite			
wash	1800		
shale & lime	1828		
shale	1846		
lime & granite			
wash	1870		
shale & granite			
wash	1940		
shale & lime &			
granite wash	1959		
sand	1965		
shale & lime	1969		
sand	1972		
lime & shale sand			
streaks	2003		
hert sdy & lime	2013		
lime chert	2018		
shale sdy	2028		
shale	2040		
sand	2054		
shale	2094		